# PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS

			CITY OF BLYTHE, CALIFOR	NIA
GENERAL NOTES	ROAD CONSTRUCTION GE	NERAL NO	TES	
<ol> <li>ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE STANDARD DETAILS AND SPECIFICATIONS AND SPECIFICATION PLANT PROVIDED ALL TRANSPORTATION AND MODICE POSTCOTION PLANT PROVIDED ALL TRANSPORTATION AND MODICE DESIT OF AWARDED AND SPECIFICATION PLANT PROVIDED ALL TRANSPORTATION AND MODICE DESIT OF AWARDED AND SPECIFICATION PLANT PROVIDED ALL TRANSPORTATION AND MODICE DESIT OF AWARDED AND SPECIFICATION PLANT PROVIDED ALL TRANSPORTATION AND MODICE DESIT OF AWARDED AND SPECIFICATION AND MODIFIES AND AWARDED AWARDE</li></ol>	<ol> <li>A. H. WERNEN HER COMMENSATION AND THE ADMITCHING THAT IS AND SECOND THAT ADMITCHING AD</li></ol>	GEOTECHNICAL INVESTI PLACE, SPREAD, WATER 14. OBSERVATIONS AND COI FILLING AND COMPACTIN CONSTRUCTED IN ACCOI 15. IN THE CASE OF CONFLIC PROJECT BY THE GEOTE NOTES. 16. THE CONTRACTOR IS TO POLE REMOVAL, ADJUST ADJUSTMENTS. 17. IT SHALL BE THE CONTR/		LOCATION MAP
The Holt Group	REVISIONS: APPROVE	ZED DATE DESIG	GN BY:       ELEVATION:       EL= 391.57'         VG       LOCATION:       ET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8 M)	PREPARED UNDER THE DIRE



UNAUTHORIZED CHANGES & USES: The engineer preparing these plans will not be for, or liable for, unauthorized changes to or uses of these plans. All changes to the plan must be in writing and must be approved by the preparer of these plans.

 201 E. HOBSONWAY
 1601 N. IMPERIAL AVE.
 36951 COOK STREET, STE. 103

 BLYTHE, CA 92225
 EL CENTRO, CA 92243
 PALM DESERT, CA 92211


 PHONE :
 (760) 922-4658
 PHONE :
 (760) 337-3883

 FAX :
 (760) 922-4660
 FAX :
 (760) 337-5997

ENGINEERING PLANNING SURVEYING

The Holt Group 

CTION GEN	NERAL NOTES								
ND SPECIFICATIONS	AREAS TO BE FILLED SHALL BE SUFFICIE	E OBSERVATION OF A QUALIFIED GEOTECHNICAL ENGINEER. ALL NTLY PREPARED AND ALL FILL SHALL BE PLACED IN ACCORDANCE	LO	CATION MAP			UTILITY PI	JRVEYORS	
E AT THE PUBLIC HALL CONFORM TO OB SITE THE SAFETY OF D SHALL NOT BE Y AND HOLD THE L OR ALLEGED, IN PLAN", PREPARED ON OF WORKERS), ED TO AND BE PRIOR TO ANY IS, FLAGMEN OR AFFIC CONTROL DMMENCEMENT OF ROPER POSITION ERMINES THAT THE AND SAFETY FETY, ALL WORK BEEN CORRECTED. ITY ADJACENT TO HE CONTRACTOR NCING WORK. THE BH BE DERGROUND ISBEFORE CORDANCE WITH ISPECTION EN (15) MINUTES OF INTRACTOR MAY BE ROLL HOUR FOR NS. THE FINISHED DIGN ELEVATION. REGATE BASE SIGN THICKNESS. A BTAINED BY THE ITY, 95% MAXIMUM IT THE OF: NATIVE ER SUBGRADE. CONFORM TO THE NS (LATEST PHALTIC CONCRETE PRIOR TO USE ON UCTED IN TWO (2) BE A MINIMUM VE HUNDREDTHS OF DOW TH PG70-10 CRETE". , HEATED SCREED, ARD DOP ACTION WILL OF CALIFORNIA HALL BE OF THE DE WITH PG70-10 CRETE". , HEATED SCREED, ARD DOP ACTION WILL OF ACTION WILL OF ACTION BE ISIGN THICKNESS MANUFACTURERS	<ul> <li>AREAS TO BE FILLED SHALL BE SUFFICIE WITH THE RECOMMENDED GRADING SPE GEOTECHNICAL INVESTIGATION FOR THIS PLACE, SPREAD, WATER AND COMPACT F</li> <li>14. OBSERVATIONS AND COMPACTION TESTS FILLING AND COMPACTING OPERATIONS CONSTRUCTED IN ACCORDANCE WITH E/</li> <li>15. IN THE CASE OF CONFLICTS, THE REQUIR PROJECT BY THE GEOTECHNICAL ENGINE NOTES.</li> <li>16. THE CONTRACTOR IS TO COORDINATE TH POLE REMOVAL, ADJUSTING WATER BLOW ADJUSTMENTS.</li> </ul>	INTLY PREPARED AND ALL FILL SHALL BE PLACED IN ACCORDANCE CIFICATIONS AND SPECIAL PROVISIONS ATTACHED TO THE S PROJECT. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ILL IN STRICT ACCORDANCE WITH THESE SPECIFICATIONS. S SHALL BE MADE BY THE GEOTECHNICAL ENGINEER DURING THE SO THAT HE CAN STATE THAT IN HIS OPINION THE FILL WAS ARTHWORK SPECIFICATIONS. MEMENTS OF THE EARTHWORK SPECIFICATIONS PREPARED FOR THE EER SHALL SUPERCEDE THE REQUIREMENTS OF THESE PLANS AND HE GRADING OPERATIONS WITH UTILITY COMPANIES PERTAINING TO MOFFS AND WATER FACILITIES TO GRADE, OR ANY OTHER UTILITY INSIBILITY TO FULLY COMPLY WITH THE STORM WATER POLLUTION OL PLAN PREPARED FOR THIS PROJECT.	Image: Not to scale         Not to scale         PROJECT         SITE         BENCHMARK:         Image: Not to scale         BENCHMARK:         Image: Not to scale         Image: Not to scale         BENCHMARK:         Image: Not to scale         Image: Not to scale	DESCRIPTION BEGINING OF CURB, TOP OF CURE LOCATED AT EASTERLY PARKING EASTERLY CURB RADIUS OF THE EASTERLY ADA HANDICAP PARKING SEE SHEET 2 FOR THE LOCATION HEET INDEX	LOT AT	GAS THE GAS COMPANY 13100 W. 14TH AVE. BLYTHE, CA 92225 CONTACT: CUSTOMER SE PHONE: (800) 427-2200 FAX: N/A ELECTRIC SOUTHERN CALIFORNIA E 505 WEST 14TH AVE. BLYTHE, CA 92225 CONTACT: VINCE NELSON PHONE: (760) 921-1609 WATER, SEWER, STORMW CITY OF BLYTHE DEPARTMENT OF PUBLIC V 440 SOUTH MAIN STREET BLYTHE, CA 92225 CONTACT: KEVIN NELSON PHONE: (760) 922-6611 FAX: (760) 922-0278 BLYTHE FIRE DEPARTMENT OU NORTH COMMERCIAL BLYTHE, CA 92225 CONTACT: RONNIE HASLEF PHONE: (760) 922-6611 FAX: N/A FIBER OPTIC ERICSSON SERVICES FOR 1141 N. JOSHUA TREE LANIG BLYTHE, CA 92225 CONTACT: REG F. LANG PHONE: (760) 922-4226 OWNER INFORMATION: PALO VERDE COLLEGE ITEM NO. ITEM NO. ITEM 1 NEW A.C. PAVEMEN 2 P.C.C. STRUCTURES 3 SIGNS/POSTS 4 POWER POLE 5 GUY WIRE	RVICE DISON COMPANY ATER VORKS SPRINT-NEXTEL CORP	TELEPHONE FRONTIER 14885 SOUTH BROADW BLYTHE, CA 92225 CONTACT: MIKE JONES PHONE: (760) 922-2700 CABLE SUDDENLINK CABLE 129 SOUTH 2ND STREE BLYTHE, CA 92225 CONTACT: GEORGE 'CC PHONE: (928) 201-0577 FAX: N/A WASTE MANAGEMENT CR&R DISPOSAL SEP CONTACT: JULIE PADIL PHONE: (760) 922-0895 PALO VERDE IRRIGATI DISTRICT 180 WEST 14TH AVENU BLYTHE, CA 92225 CONTACT: JULIE PADIL PHONE: (760) 922-3144 FAX: (760) 922-8294 DISTRICT 180 WEST 14TH AVENU BLYTHE, CA 92225 CONTACT: J.R. ECHAR PHONE: (760) 922-8294	T HIP' ACKER ICE AY LA ON JE D SYMBOL SYMBOL SYMBOL BC BTM DW EC EG FF FF FI G
D PLANS IN RED INK FURNISH THE CITY HALL NOT BE DR AND HIS IVITIES. ALL NOT BE RAISED ED INTACT. SHOULD DNAL SHALL BE R JOB SITE TY OF ALL PERSONS LIMITED TO HOLD THE CITY AND ITH THE E NEGLIGENCE OF NS. THE G SHORING, AND AFETY AND HEALTH OSHA. THESE PLANS DWLEDGE, THERE DR IS REQUIRED TO INY OTHERS NOT OF TRACTOR SHALL BE TOR. EPHONE AND ERVE ALL POSSIBLE NTEE ANY ERGROUND EVISIONS ARE			11.STRIPING PLAN			<ul> <li>6 EXISTING PALM TRE</li> <li>7 EXISTING BRUSH</li> <li>8 VARIABLE GUTTER</li> <li>9 RIGHT OF WAY</li> <li>10 EXISTING A.C. PAVE</li> <li>11 EXISTING FENCE</li> <li>12 PROPERTY LINE</li> <li>13 DRIVEWAY</li> <li>14 CLASS 2 BASE</li> </ul>			B TCC
L UNDERGROUND E CONFIRMED BY DJACENT DE UPON RAINS ARE BUILT IN INS OR FIELD DRK BY CALLING THE ESSARY STEPS TO HAT MAY RESULT ESILTING BASINS, ED.					STAMPED "FLY 1948", N MI) WEST FROM BLYTH FROM THE JUNCTION ( (235 FT) SOUTH-SOUTH BUILDING BELONGING METERS (129 FT) NORT CENTERLINE OF HOBS BARBED WIRE RIGHT-( OF THE FIRST POWER CLUB, 13.2 METERS (43) GRAVEL ROAD. THE M	EL= 391.57' BRASS DISK ON A CONCRETE M NATIONAL GEODETIC SURVEY 198 IE. 13.0 KM (8.1 MI) WEST ALONG DF U.S. HIGHWAY 95 IN BLYTHE, 1 WEST OF THE SOUTHWEST COR TO THE BLYTHE TRAP SHOOT CL TH ACROSS A GRAVEL ROAD FRO ONWAY, 26.8 METERS (88.0 FT) N DF-WAY FENCE, 24.9 METERS (81. POLE WEST OF A SPUR LINE TO 3.5 FT) NORTH OF THE CENTERLIN ARK IS 2.35 METERS N FROM A W EVEL WITH HOBSONWAY. EL= 3	11 13.0 KM (8.1 HOBSONWAY 02.1 METERS NER OF A UB, 39.3 M THE ORTH OF A 7 FT) NORTH THE TRAP IE OF THE ITNESS POST	UNDERGROUND S Call: TOL hat's below. ore you dig. 81	L FREE 1
APPROVED	VG       DRAWN BY:	ELEVATION: <u>EL= 391.57'</u> LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 M WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING SOUTH-SOUTHWEST OF THE SOUTHWEST CONNER OF A BUILDING SOUTH-SOUTHWEST OF THE SOUTHWEST COUNDER OF A BUILDING				27943 SHEET (	PARKING LOT IN THE CITY OF B CONTENT:	DE COLLEGE IMPROVEMENTS LYTHE, CALIFORNIA	SHEE 1
sponsible	VG CHECKED BY: RKH	BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF HOBSONWAY, 26.8 METERS (88.0 FT) NORTH OF A BARBED WIRE RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MAP IS 2.35 METERS N FROM A WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57'	Exp. 03-81-24 0 $Z$ $Z$ $T$	ROBERT K. HOLT, P.E. 09-01-2022 DATE		R.C.E. NO. 03/31/24 REG. EXP. LOCATIO	TITLE S	SHEET CLIENT: PALO VERDE COLLEGE	OF <b>14</b> s JOB NO. 533.00





UNAUTHORIZED CHANGES & USES: The engineer preparing these plans will not be for, or liable for, unauthorized changes to or uses of these plans. All changes to the plan must be in writing and must be approved by the preparer of these plans.


**REVISIONS**:

	APPROVED	DATE	DESIGN BY:	ELEVATION: <u>EL= 391.57'</u>		PREPARED UNDER THE DIREC
			VG	LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI)	SED ERT K. MAN	Mar 14
			DRAWN BY: VG	WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF		ROBERT K. HOLT, P.E.
be responsible plans			CHECKED BY:	HOBSONWAY, 26.8 METERS (88.0 FT) NORTH OF A BARBED WIRE RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK IS 2.35 METERS N FROM A WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57'	STATICIAL STAT	09-01-2022 DATE

LEGEND	
ITEM	SYMBOL
EXISTING P.C.C. STRUCTURES	
EXISTING A.C. PAVEMENT	
COLD PLANED 2-INCHES OF EXISTING A.C. PAVEMENT	
REMOVE AND DISPOSE EXISTING A.C. PAVEMENT	
CRACK SEAL, SLURRY SEAL	
NEW 4" A.C. PAVEMENT OVER 12"	
A.C. PAVEMENT OVERLAY AT COLD PLANED AREA.	
NEW CRACK SEAL, SLURRY SEAL	
NEW P.C.C. PAVEMENT	
INSTALLATION A.C. GRINDINGS	
EXISTING P.C.C. RIBBON GUTTER TO BE REMOVED	
EXISTING P.C.C. CONCRETE TO BE REMOVED	
MANHOLE	<b>M</b>
WATER VALVE	•
SIGNS/POSTS	<b>→</b>
BENCHMARK	÷

# BENCHMARK TABLE

TBM #	ELEVATION	DESCRIPTION
BM#1	391.69	BEGINING OF CURB, TOP OF CURB LOCATED AT EASTERLY CURB RADIUS OF ADA HANDICAP PARKING SPACE



	2	PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS IN THE CITY OF BLYTHE, CALIFORNIA	SHEET
H		SHEET CONTENT:	<u> </u>
<u>.</u>	27943 R.C.E. NO.	SHEET INDEX	of 14 sheets
_	03/31/24		JOB NO.
_	REG. EXP.	LOCATION: BLYTHE, CA. CLIENT: PALO VERDE COLLEGE	533.007



MATCH LINE SEE SHEET 5


c/SHO		NO. REVISIONS:	APPROVED	DATE	DESIGN BY:	ELEVATION: <u>EL= 391.57'</u>		PREPARED UNDER THE DIRECT
∩∕ xoqo	The Holt Group				VG	LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI)	SHOPESSION AL	And A
a / Drop	ENGINEERING PLANNING SURVEYING				DRAWN BY:	WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING	SEORER K. AND Z	Nello K. All
VGarci					VG	BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF HOBSONWAY, 26.8 METERS (88.0 FT) NORTH OF A BARBED WIRE	Exp. 03-81-24 *	ROBERT K. HOLT, P.E.
Jsers	201 E. HOBSONWAY         1601 N. IMPERIAL AVE.         36951 COOK STREET, STE. 103           BLYTHE, CA 92225         EL CENTRO, CA 92243         PALM DESERT, CA 92211           PHONE :         (760) 922-4658         PHONE :         (760) 337-3883           FAX :         (760) 922-4660         FAX :         (760) 337-5997	UNAUTHORIZED CHANGES & USES: The engineer preparing these plans will not be responsible for, or liable for, unauthorized changes to or uses of these plans. All changes to the plans			CHECKED BY:	RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK	OF THE OF CALIFORNIE	09-01-2022
_ر ت	FAX: (760) 922-4660 FAX: (760) 337-5997	must be in writing and must be approved by the preparer of these plans.				IS 2.35 METERS N FROM A WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57'	5	DATE

- **EXISTING KEYNOTES**
- (1) EXISTING SIDEWALK TO REMAIN.
- (2) EXISTING DRIVEWAY TO REMAIN.
- (3) EXISTING BARRIER CURB TO REMAIN.
- (4) EXISTING CURB AND GUTTER TO REMAIN.
- (5) EXISTING RIBBON GUTTER TO REMAIN.
- (6) EXISTING BUILDING TO REMAIN.
- (7) EXISTING P.C.C. SPANDREL TO REMAIN.
- (8) EXISTING P.C.C. PARKING LOT TO REMAIN.
- DEMOLITION KEYNOTES
- 1 COLD PLANE EXISTING A.C. PAVEMENT FOR A DEPTH OF 1-1/2-INCH, AND APPLY RUBBERIZED CRACK SEALANT TO THE EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 2 PRIOR THE APPLICATION OF THE RUBBERIZED CRACK SEALANT TO EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 3 REMOVE AND DISPOSE OF THE EXISTING A.C. PAVEMENT AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 4 CONTRACTOR TO LOWER EXISTING SANITARY SEWER MANHOLE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 5 CONTRACTOR TO LOWER EXISTING DOMESTIC WATER VALVE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 6 SAWCUT THE EXISTING A.C. PAVEMENT TO THE FULL DEPTH OF THE A.C. PAVEMENT.
- 7 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. HANDICAP RAMP AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 8 REMOVE AND DISPOSE OF THE EXISTING P.C.C. RIBBON GUTTER AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 9 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. CONCRETE AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.

- AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT AFTER COLD PLAINING PROCESS AND SWEEPING ACTIVITIES HAVE BEEN COMPLETED. THE CONTRACTOR SHALL INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT. SEE DETAIL A ON SHEET 14.
- 2 THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT SURFACE AND APPLY AN (SEALMASTER, GUARDTOP) ASPHALT SEAL COAT OR AN APPROVED EQUAL. SEE DETAIL B ON SHEET 14.
- ③ INSTALL 6-INCHES OF P.C.C. CONCRETE OVER 6-INCHES OF CLASS 2 BASE WITHIN THE P.C.C. PARKING LOT AREA. COMPACT THE CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. THE CONTRACTOR SHALL INSTALL # 5 REINFORCING BARS 18 INCHES ON CENTER EACH WAY. THE CONTRACTOR SHALL INSTALL NUMBER 4 REINFORCING BARS 6-INCHES IN LENGTH. THE # 4 BARS SHALL BE DOWELED FOR A HORIZONTAL DISTANCE OF 3-INCHES INTO THE EXISTING P.C.C. PARKING LOT, BARRIER CURB/RIBBON GUTTER AND 3-INCHES ABOVE THE EXISTING BOTTOM OF THE P.C.C. CONCRETE. THE DOWELS SHALL BE PLACED 2 FEET ON CENTER ALONG THE LENGTH OF THE EXISTING SAWCUT P.C.C. BARRIER CURB/RIBBON GUTTER. SEE DETAIL C ON SHEET 14.
- (4) INSTALL 3-INCHES OF A.C. PAVEMENT OVER 8-INCHES OF CLASS 2 BASE. COMPACT CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. SEE DETAIL D ON SHEET 14.
- 5 ADJUST THE EXISTING SANITARY SEWER MAHNOLE FRAME AND COVER TO FINISH GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE A 12-INCH WIDE, 12-INCH DEEP, 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE MANHOLE.
- $\langle \widehat{\mathbf{6}} \rangle$  CONTRACTOR TO ADJUST WATER VALVE RISER TO FINISH DESIGN GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE AN 8-INCH DEEP 8-INCH WIDE 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE WATER VALE RISER.
- $\langle \overline{7} \rangle$  INSTALL HANDICAP RAMP PER CALTRANS STANDARD PLAN A88A.
- (8) INSTALL 3-INCHES OF THE PARKING LOT A.C. GRINDINGS AS ILLUSTRATED ON SHEET 12 OF THE IMPROVEMENTS PLANS. COMPACT A.C. GRINDINGS MATERIAL TO 90 PERCENT MAXIMUM DENSITY PER ASTM D-1557.


### NOTE:

1. AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL ADDRESS CRACKS THAT ARE GREATER THAN 1.5-INCHES THICK AS FOLLOWS. THE CONTRACTOR SHALL SAWCUT THE CRACK TO THE FULL DEPTH OF THE A.C. PAVEMENT TO A DISTANCE OF 6-INCHES ON EACH SIDE FROM THE CENTERLINE OF THE CRACK . THE CONTRACTOR SHALL MAINTAIN A 1-FOOT WIDE TRENCH FROM THE CENTERLINE OF THE CRACK. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF THE REMAINING 1.5-INCHES OF THE EXISTING ASPHALT. AFTER THE REMOVAL OF THE ASPHALT THE CONTRACTOR SHALL INSTALL 1.5-INCHES OF A.C. PAVEMENT TO PATCH THE REMOVED ASPHALT TO THE GRINDED PAVEMENT SURFACE. THE CONTRACTOR SHALL THAN INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT.



SCALE 1"= 30'

	: :		PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS IN THE CITY OF BLYTHE, CALIFORNIA				
HH DLT, P.E.	27943 R.C.E. NO.	SHEET CONT	SHEET CONTENT: IMPROVEMENT PLAN				
	03/31/24 REG. EXP.			T	PALO VERDE COLLEGE	OF <u>14</u> SHEETS JOB NO. 533.007	
	REG. EXP.	LOCATION:	BLYTHE, CA.	CLIENT:	PALO VERDE COLLEGE		




	APPROVED	DATE	DESIGN BY:	ELEVATION: <u>EL= 391.57'</u>		PREPARED UNDER THE DIRE
			VG	LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI)	SED PROFESSION	A vil 1
			DRAWN BY: VG	WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING		- Nella K H
				BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF HOBSONWAY, 26.8 METERS (88.0 FT) NORTH OF A BARBED WIRE	Exp. 03-81-24 *	ROBERT K. HOLT, P.
e responsible			CHECKED BY:	RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK	STATE CIVIL ORN	09-01-2022
lans			RKH	IS 2.35 METERS N FROM A WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57'	E OF CALIFO	DATE

- **EXISTING KEYNOTES**
- (1) EXISTING SIDEWALK TO REMAIN.
- (2) EXISTING DRIVEWAY TO REMAIN.
- (3) EXISTING BARRIER CURB TO REMAIN.
- (4) EXISTING CURB AND GUTTER TO REMAIN.
- (5) EXISTING RIBBON GUTTER TO REMAIN.
- (6) EXISTING BUILDING TO REMAIN.
- (7) EXISTING P.C.C. SPANDREL TO REMAIN.
- (8) EXISTING P.C.C. PARKING LOT TO REMAIN.
- **DEMOLITION KEYNOTES**
- 1 COLD PLANE EXISTING A.C. PAVEMENT FOR A DEPTH OF 1-1/2-INCH, AND APPLY RUBBERIZED CRACK SEALANT TO THE EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 2 PRIOR THE APPLICATION OF THE RUBBERIZED CRACK SEALANT TO EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 3 REMOVE AND DISPOSE OF THE EXISTING A.C. PAVEMENT AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 4 CONTRACTOR TO LOWER EXISTING SANITARY SEWER MANHOLE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 5 CONTRACTOR TO LOWER EXISTING DOMESTIC WATER VALVE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 6 SAWCUT THE EXISTING A.C. PAVEMENT TO THE FULL DEPTH OF THE A.C. PAVEMENT.
- 7 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. HANDICAP RAMP AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 8 REMOVE AND DISPOSE OF THE EXISTING P.C.C. RIBBON GUTTER AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 9 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. CONCRETE AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 10 REMOVE AND DISPOSE OF P.C.C SLAB AND 4-FOOT HIGH MISCELLANEOUS MASONRY/BRICK WALL RESTING ON EXISTING ASPHALT PAVEMENT.

- AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT AFTER COLD PLAINING PROCESS AND SWEEPING ACTIVITIES HAVE BEEN COMPLETED. THE CONTRACTOR SHALL INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT. SEE DETAIL A ON SHEET 14.
- $\langle 2 \rangle$  THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT SURFACE AND APPLY AN (SEALMASTER, GUARDTOP) ASPHALT SEAL COAT OR AN APPROVED EQUAL. SEE DETAIL B ON SHEET 14.
- (3) INSTALL 6-INCHES OF P.C.C. CONCRETE OVER 6-INCHES OF CLASS 2 BASE WITHIN THE P.C.C. PARKING LOT AREA. COMPACT THE CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. THE CONTRACTOR SHALL INSTALL # 5 REINFORCING BARS 18 INCHES ON CENTER EACH WAY. THE CONTRACTOR SHALL INSTALL NUMBER 4 REINFORCING BARS 6-INCHES IN LENGTH. THE # 4 BARS SHALL BE DOWELED FOR A HORIZONTAL DISTANCE OF 3-INCHES INTO THE EXISTING P.C.C. PARKING LOT, BARRIER CURB/RIBBON GUTTER AND 3-INCHES ABOVE THE EXISTING BOTTOM OF THE P.C.C. CONCRETE. THE DOWELS SHALL BE PLACED 2 FEET ON CENTER ALONG THE LENGTH OF THE EXISTING SAWCUT P.C.C. BARRIER CURB/RIBBON GUTTER. SEE DETAIL C ON SHEET 14.
- (4) INSTALL 3-INCHES OF A.C. PAVEMENT OVER 8-INCHES OF CLASS 2 BASE. COMPACT CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. SEE DETAIL D ON SHEET 14.
- (5) ADJUST THE EXISTING SANITARY SEWER MAHNOLE FRAME AND COVER TO FINISH GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE A 12-INCH WIDE, 12-INCH DEEP, 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE MANHOLE.
- $\langle 6 \rangle$  CONTRACTOR TO ADJUST WATER VALVE RISER TO FINISH DESIGN GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE AN 8-INCH DEEP 8-INCH WIDE 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE WATER VALE RISER.
- $\langle \overline{7} \rangle$  INSTALL HANDICAP RAMP PER CALTRANS STANDARD PLAN A88A.
- (8) INSTALL 3-INCHES OF THE PARKING LOT A.C. GRINDINGS AS ILLUSTRATED ON SHEET 12 OF THE IMPROVEMENTS PLANS. COMPACT A.C. GRINDINGS


NOTE:

1. AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL ADDRESS CRACKS THAT ARE GREATER THAN 1.5-INCHES THICK AS FOLLOWS. THE CONTRACTOR SHALL SAWCUT THE CRACK TO THE FULL DEPTH OF THE A.C. PAVEMENT TO A DISTANCE OF 6-INCHES ON EACH SIDE FROM THE CENTERLINE OF THE CRACK . THE CONTRACTOR SHALL MAINTAIN A 1-FOOT WIDE TRENCH FROM THE CENTERLINE OF THE CRACK. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF THE REMAINING 1.5-INCHES OF THE EXISTING ASPHALT. AFTER THE REMOVAL OF THE ASPHALT THE CONTRACTOR SHALL INSTALL 1.5-INCHES OF A.C. PAVEMENT TO PATCH THE REMOVED ASPHALT TO THE GRINDED PAVEMENT SURFACE. THE CONTRACTOR SHALL THAN INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT.



SCALE 1"= 30'

	N OF:		PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS IN THE CITY OF BLYTHE, CALIFORNIA				
<u>Р.Е.</u>	27943 	SHEET CONTENT: IMPROVEMENT PLAN				4  of 14 sheets	
	03/31/24					JOB NO.	
	REG. EXP.	LOCATION:	BLYTHE, CA.	CLIENT:	PALO VERDE COLLEGE	533.007	




- EXISTING KEYNOTES
- 1 EXISTING SIDEWALK TO REMAIN.
- (2) EXISTING DRIVEWAY TO REMAIN.
- (3) EXISTING BARRIER CURB TO REMAIN.
- (4) EXISTING CURB AND GUTTER TO REMAIN.
- (5) EXISTING RIBBON GUTTER TO REMAIN.
- (6) EXISTING BUILDING TO REMAIN.
- (7) EXISTING P.C.C. SPANDREL TO REMAIN.
- (8) EXISTING P.C.C. PARKING LOT TO REMAIN.
- DEMOLITION KEYNOTES
- 1 COLD PLANE EXISTING A.C. PAVEMENT FOR A DEPTH OF 1-1/2-INCH, AND APPLY RUBBERIZED CRACK SEALANT TO THE EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 2 PRIOR THE APPLICATION OF THE RUBBERIZED CRACK SEALANT TO EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 3 REMOVE AND DISPOSE OF THE EXISTING A.C. PAVEMENT AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 4 CONTRACTOR TO LOWER EXISTING SANITARY SEWER MANHOLE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 5 CONTRACTOR TO LOWER EXISTING DOMESTIC WATER VALVE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 6 SAWCUT THE EXISTING A.C. PAVEMENT TO THE FULL DEPTH OF THE A.C. PAVEMENT.
- 7 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. HANDICAP RAMP AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 8 REMOVE AND DISPOSE OF THE EXISTING P.C.C. RIBBON GUTTER AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 9 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. CONCRETE AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.

- AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE. THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT AFTER COLD PLAINING PROCESS AND SWEEPING ACTIVITIES HAVE BEEN COMPLETED. THE CONTRACTOR SHALL INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT. SEE DETAIL A ON SHEET 14.
- 2 THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT SURFACE AND APPLY AN (SEALMASTER, GUARDTOP) ASPHALT SEAL COAT OR AN APPROVED EQUAL. SEE DETAIL B ON SHEET 14.
- (3) INSTALL 6-INCHES OF P.C.C. CONCRETE OVER 6-INCHES OF CLASS 2 BASE WITHIN THE P.C.C. PARKING LOT AREA. COMPACT THE CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. THE CONTRACTOR SHALL INSTALL # 5 REINFORCING BARS 18 INCHES ON CENTER EACH WAY. THE CONTRACTOR SHALL INSTALL NUMBER 4 REINFORCING BARS 6-INCHES IN LENGTH. THE # 4 BARS SHALL BE DOWELED FOR A HORIZONTAL DISTANCE OF 3-INCHES INTO THE EXISTING P.C.C. PARKING LOT, BARRIER CURB/RIBBON GUTTER AND 3-INCHES ABOVE THE EXISTING BOTTOM OF THE P.C.C. CONCRETE. THE DOWELS SHALL BE PLACED 2 FEET ON CENTER ALONG THE LENGTH OF THE EXISTING SAWCUT P.C.C. BARRIER CURB/RIBBON GUTTER. SEE DETAIL C ON SHEET 14.
- (4) INSTALL 3-INCHES OF A.C. PAVEMENT OVER 8-INCHES OF CLASS 2 BASE. COMPACT CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. SEE DETAIL D ON SHEET 14.
- (5) ADJUST THE EXISTING SANITARY SEWER MAHNOLE FRAME AND COVER TO FINISH GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE A 12-INCH WIDE, 12-INCH DEEP, 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE MANHOLE.
- (6) CONTRACTOR TO ADJUST WATER VALVE RISER TO FINISH DESIGN GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE AN 8-INCH DEEP 8-INCH WIDE 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE WATER VALE RISER.
- $\langle \overline{7} \rangle$  INSTALL HANDICAP RAMP PER CALTRANS STANDARD PLAN A88A.
- (8) INSTALL 3-INCHES OF THE PARKING LOT A.C. GRINDINGS AS ILLUSTRATED ON SHEET 12 OF THE IMPROVEMENTS PLANS. COMPACT A.C. GRINDINGS MATERIAL TO 00 DEDOCIMIT MAXIMUM DEMOLTLY DED ACTA D 4557

### NOTE:


AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL ADDRESS CRACKS THAT ARE GREATER THAN 1.5-INCHES THICK AS FOLLOWS. THE CONTRACTOR SHALL SAWCUT THE CRACK TO THE FULL DEPTH OF THE A.C. PAVEMENT TO A DISTANCE OF 6-INCHES ON EACH SIDE FROM THE CENTERLINE OF THE CRACK. THE CONTRACTOR SHALL MAINTAIN A 1-FOOT WIDE TRENCH FROM THE CENTERLINE OF THE CRACK. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF THE REMAINING 1.5-INCHES OF THE EXISTING ASPHALT. AFTER THE REMOVAL OF THE ASPHALT THE CONTRACTOR SHALL INSTALL 1.5-INCHES OF A.C. PAVEMENT TO PATCH THE REMOVED ASPHALT TO THE GRINDED PAVEMENT SURFACE. THE CONTRACTOR SHALL THAN INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT.



SCALE 1"= 30'

PERVISION OF:		PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS IN THE CITY OF BLYTHE, CALIFORNIA				
<u>27943</u> R.C.E. NO.	SHEET CONT	5 of_ <u>14</u>				
03/31/24					JOB NO.	
REG. EXP.	LOCATION:	BLYTHE, CA.	CLIENT:	PALO VERDE COLLEGE	533.007	

ATCH LINE SEE SHEET 6



- **EXISTING KEYNOTES**
- (1) EXISTING SIDEWALK TO REMAIN.
- (2) EXISTING DRIVEWAY TO REMAIN.
- (3) EXISTING BARRIER CURB TO REMAIN.
- (4) EXISTING CURB AND GUTTER TO REMAIN.
- (5) EXISTING RIBBON GUTTER TO REMAIN.
- (6) EXISTING BUILDING TO REMAIN.
- (7) EXISTING P.C.C. SPANDREL TO REMAIN.
- (8) EXISTING P.C.C. PARKING LOT TO REMAIN.
- DEMOLITION KEYNOTES
- 1 COLD PLANE EXISTING A.C. PAVEMENT FOR A DEPTH OF 1-1/2-INCH, AND APPLY RUBBERIZED CRACK SEALANT TO THE EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 2 PRIOR THE APPLICATION OF THE RUBBERIZED CRACK SEALANT TO EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 3 REMOVE AND DISPOSE OF THE EXISTING A.C. PAVEMENT AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 4 CONTRACTOR TO LOWER EXISTING SANITARY SEWER MANHOLE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 5 CONTRACTOR TO LOWER EXISTING DOMESTIC WATER VALVE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 6 SAWCUT THE EXISTING A.C. PAVEMENT TO THE FULL DEPTH OF THE A.C. PAVEMENT.
- 7 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. HANDICAP RAMP AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 8 REMOVE AND DISPOSE OF THE EXISTING P.C.C. RIBBON GUTTER AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 9 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. CONCRETE AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.

- AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT AFTER COLD PLAINING PROCESS AND SWEEPING ACTIVITIES HAVE BEEN COMPLETED. THE CONTRACTOR SHALL INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT. SEE DETAIL A ON SHEET 14.
- (2) THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT SURFACE AND APPLY AN (SEALMASTER, GUARDTOP) ASPHALT SEAL COAT OR AN APPROVED EQUAL. SEE DETAIL B ON SHEET 14.
- (3) INSTALL 6-INCHES OF P.C.C. CONCRETE OVER 6-INCHES OF CLASS 2 BASE WITHIN THE P.C.C. PARKING LOT AREA. COMPACT THE CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. THE CONTRACTOR SHALL INSTALL # 5 REINFORCING BARS 18 INCHES ON CENTER EACH WAY. THE CONTRACTOR SHALL INSTALL NUMBER 4 REINFORCING BARS 6-INCHES IN LENGTH. THE # 4 BARS SHALL BE DOWELED FOR A HORIZONTAL DISTANCE OF 3-INCHES INTO THE EXISTING P.C.C. PARKING LOT, BARRIER CURB/RIBBON GUTTER AND 3-INCHES ABOVE THE EXISTING BOTTOM OF THE P.C.C. CONCRETE. THE DOWELS SHALL BE PLACED 2 FEET ON CENTER ALONG THE LENGTH OF THE EXISTING SAWCUT P.C.C. BARRIER CURB/RIBBON GUTTER. SEE DETAIL C ON SHEET 14.
- (4) INSTALL 3-INCHES OF A.C. PAVEMENT OVER 8-INCHES OF CLASS 2 BASE. COMPACT CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. SEE DETAIL D ON SHEET 14.
- (5) ADJUST THE EXISTING SANITARY SEWER MAHNOLE FRAME AND COVER TO FINISH GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE A 12-INCH WIDE, 12-INCH DEEP, 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE MANHOLE.
- $\langle 6 \rangle$  CONTRACTOR TO ADJUST WATER VALVE RISER TO FINISH DESIGN GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE AN 8-INCH DEEP 8-INCH WIDE 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE WATER VALE RISER.
- $\langle \overline{7} \rangle$  INSTALL HANDICAP RAMP PER CALTRANS STANDARD PLAN A88A.
- (8) INSTALL 3-INCHES OF THE PARKING LOT A.C. GRINDINGS AS ILLUSTRATED ON SHEET 12 OF THE IMPROVEMENTS PLANS. COMPACT A.C. GRINDINGS
- NOTE: AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL ADDRESS CRACKS THAT ARE GREATER THAN 1.5-INCHES THICK AS FOLLOWS. THE CONTRACTOR SHALL SAWCUT THE CRACK TO THE FULL DEPTH OF THE A.C. PAVEMENT TO A DISTANCE OF 6-INCHES ON EACH SIDE FROM THE CENTERLINE OF THE CRACK. THE CONTRACTOR SHALL MAINTAIN A 1-FOOT WIDE TRENCH FROM THE CENTERLINE OF THE CRACK. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF THE REMAINING 1.5-INCHES OF THE EXISTING ASPHALT. AFTER THE REMOVAL OF THE ASPHALT THE CONTRACTOR SHALL INSTALL 1.5-INCHES OF A.C. PAVEMENT TO PATCH THE REMOVED ASPHALT TO THE GRINDED PAVEMENT SURFACE. THE CONTRACTOR SHALL THAN INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT.

CLIENT: PALO VERDE COLLEGE


## BENCHMARK TABLE

	TBM #	ELEVATION	DESC	RIPTION						
	BM#1	391.69	LOCAT	IING OF CURB, T FED AT EASTERL IANDICAP PARKI	Y CURB RAD	IUS OF				
						30	0	30	60	90
								SCALE 1"= 3	30'	
ERVI	SION OF:				PARKIN	NG LOT IN	E COLLEGE APROVEMEN			SHEET
-				SHEET CONT		CITY OF BLY	THE, CALIFORN	ΙΑ		6
		27943 R.C.E. NO.	_			OVEME	ENT PL/	۹N		of <u>14</u> sheets


03/31/24 REG. EXP.


LOCATION: BLYTHE, CA.


JOB NO. 533.007



**BLOWUP DETAIL A** 







	APPROVED	DATE	DESIGN BY:	ELEVATION: <u>EL= 391.57'</u>		PREPARED UNDER THE DIRECT SUPERVISION	
			VG	LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI)	SED BERT K. THE	Chr / JAH	
			DRAWN BY: VG	WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF	27943	ROBERT K. HOLT, P.E.	
be responsible blans		CHECKED BY: 	HOBSONWAY, 26.8 METERS (88.0 FT) NORTH OF A BARBED WIRE RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK IS 2.35 METERS N FROM A WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57'	OF CALIFORNI	08-09-2022 DATE		

**BLOWUP DETAIL C** 

EXISTING KEYNOTES

- (1) EXISTING SIDEWALK TO REMAIN.
- (2) EXISTING DRIVEWAY TO REMAIN.
- (3) EXISTING BARRIER CURB TO REMAIN.
- (4) EXISTING CURB AND GUTTER TO REMAIN.
- (5) EXISTING RIBBON GUTTER TO REMAIN.
- (6) EXISTING BUILDING TO REMAIN.
- (7) EXISTING P.C.C. SPANDREL TO REMAIN.
- (8) EXISTING P.C.C. PARKING LOT TO REMAIN.

### DEMOLITION KEYNOTES

- 1 COLD PLANE EXISTING A.C. PAVEMENT FOR A DEPTH OF 1-1/2-INCH, AND APPLY RUBBERIZED CRACK SEALANT TO THE EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 2 PRIOR THE APPLICATION OF THE RUBBERIZED CRACK SEALANT TO EXISTING A.C. PAVEMENT CRACKS. REMOVE ANY LOOSE MATERIAL (AIR PRESSURE) FROM EXISTING CRACKS PRIOR TO SEALANT APPLICATION. REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.
- 3 REMOVE AND DISPOSE OF THE EXISTING A.C. PAVEMENT AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 4 CONTRACTOR TO LOWER EXISTING SANITARY SEWER MANHOLE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 5 CONTRACTOR TO LOWER EXISTING DOMESTIC WATER VALVE FRAME AND COVER TO 0.30 FEET BELOW GRADE PRIOR TO PAVING ACTIVITIES.
- 6 SAWCUT THE EXISTING A.C. PAVEMENT TO THE FULL DEPTH OF THE A.C. PAVEMENT.
- 7 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. HANDICAP RAMP AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 8 REMOVE AND DISPOSE OF THE EXISTING P.C.C. RIBBON GUTTER AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- 9 SAWCUT THE EXISTING P.C.C. CONCRETE TO THE FULL DEPTH OF THE P.C.C. CONCRETE. REMOVE AND DISPOSE OF THE EXISTING P.C.C. CONCRETE AND UNDERLYING MATERIAL TO SUBBASE DESIGN GRADE.
- CONSTRUCTION KEYNOTES
- AFTER THE 1-1/2-INCH COLD PLANING PROCESS HAS BEEN COMPLETED THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT AFTER COLD PLAINING PROCESS AND SWEEPING ACTIVITIES HAVE BEEN COMPLETED. THE CONTRACTOR SHALL INSTALL 1-1/2 INCHES OF A 1/2-INCH CONVENTIONAL A.C. PAVEMENT. SEE DETAIL A ON SHEET 14.
- (2) THE CONTRACTOR SHALL CLEAN AND SWEEP THE AC PAVEMENT SURFACE, THE CONTRACTOR SHALL CLEAN ALL CRACKS FROM DEBRIS. AFTER SWEEPING ACTIVITIES HAVE BEEN COMPLETED THE CONTRACTOR SHALL CRACK SEAL THE EXISTING A.C. PAVEMENT SURFACE AND APPLY AN (SEALMASTER, GUARDTOP) ASPHALT SEAL COAT OR AN APPROVED EQUAL. SEE DETAIL B ON SHEET 14.
- (3) INSTALL 6-INCHES OF P.C.C. CONCRETE OVER 6-INCHES OF CLASS 2 BASE WITHIN THE P.C.C. PARKING LOT AREA. COMPACT THE CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. THE CONTRACTOR SHALL INSTALL # 5 REINFORCING BARS 18 INCHES ON CENTER EACH WAY. THE CONTRACTOR SHALL INSTALL NUMBER 4 REINFORCING BARS 6-INCHES IN LENGTH. THE # 4 BARS SHALL BE DOWELED FOR A HORIZONTAL DISTANCE OF 3-INCHES INTO THE EXISTING P.C.C. PARKING LOT, BARRIER CURB/RIBBON GUTTER AND 3-INCHES ABOVE THE EXISTING BOTTOM OF THE P.C.C. CONCRETE. THE DOWELS SHALL BE PLACED 2 FEET ON CENTER ALONG THE LENGTH OF THE EXISTING SAWCUT P.C.C. BARRIER CURB/RIBBON GUTTER. SEE DETAIL C ON SHEET 14.
- (4) INSTALL 3-INCHES OF A.C. PAVEMENT OVER 8-INCHES OF CLASS 2 BASE. COMPACT CLASS 2 BASE MATERIAL TO 95 PERCENT MAXIMUM DENSITY PER ASTM D-1557. SEE DETAIL D ON SHEET 14.
- $\langle 5 \rangle$  ADJUST THE EXISTING SANITARY SEWER MAHNOLE FRAME AND COVER TO FINISH GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE A 12-INCH WIDE, 12-INCH DEEP, 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE MANHOLE.
- $\langle 6 \rangle$  CONTRACTOR TO ADJUST WATER VALVE RISER TO FINISH DESIGN GRADE AFTER PAVING OPERATIONS ARE COMPLETE. PLACE AN 8-INCH DEEP 8-INCH WIDE 5,000 PSI CONCRETE RING AROUND THE EXTERIOR CIRCUMFERENCE OF THE WATER VALE RISER.
- $\langle \overline{7} \rangle$  INSTALL HANDICAP RAMP PER CALTRANS STANDARD PLAN A88A.
- (8) INSTALL 3-INCHES OF THE PARKING LOT A.C. GRINDINGS AS ILLUSTRATED ON SHEET 12 OF THE IMPROVEMENTS PLANS. COMPACT A.C. GRINDINGS

BENCHMARK TABLE	

TBM #	ELEVATION	DESCRIPTION
BM#1	391.69	BEGINING OF CURB, TOP OF CURB LOCATED AT EASTERLY CURB RADIUS OF ADA HANDICAP PARKING SPACE

			30	0	30	60	90
					SCALE 1"= 30'	I	
ON OF:				SHEET 7			
	07040	SHEET CONT	TENT:				<u> </u>
-	27943 R.C.E. NO.		BLOWUF	P DETAIL		o	р <mark>_14</mark> _унеет
	03/31/24					JC	OB NO.
-	REG. EXP.	LOCATION:	BLYTHE, CA.	CLIENT:	PALO VERDE COLLEG	E	533.007



36951 COOK STREET, STE. 10 PALM DESERT, CA 92211 PHONE : (760) 427-8533

1601 N. IMPERIAL AVE. EL CENTRO, CA 92243 PHONE : (760) 337-3883 FAX : (760) 337-5997

NO.	REVISIONS:	APPROVED	DATE	DESIGN BY:	ELEVATION:		PREPARED UNDER THE DIRECT S
				VG	LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI)	PROFESSION ROBERT K. MARKEN	Maril 10
				DRAWN BY: VG	WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF HOBSONWAY, 26.8 METERS (88.0 FT) NORTH OF A BARBED WIRE	97943 III	ROBERT K. HOLT, P.E.
for, or lia	THORIZED CHANGES & USES: The engineer preparing these plans will not be responsible liable for, unauthorized changes to or uses of these plans. All changes to the plans e in writing and must be approved by the preparer of these plans.			CHECKED BY:	RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK IS 2.35 METERS N FROM A WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57'	OF THE OF CALIFORNIE	09-01-2022 DATE

			SCALE 1"= 30'			
SUPERVISION OF:			PALO VERD PARKING LOT I IN THE CITY OF BL			SHEET
A Contraction of the second se		SHEET CON	TENT:			- 8
1	27943 R.C.E. NO.		STRIPIN	G PLAN		of 14 sheets
_	03/31/24					JOB NO.
	REG. EXP.	LOCATION:	BLYTHE, CA.	CLIENT:	PALO VERDE COLLEGE	533.007

 $\infty$ 

# 5 INSTALL AN INTERNATIONAL SYMBOL OF ACCESSIBILITY (ISA) BLUE SYMBOL PER CALTRANS STANDARD A24C AND CALTRANS STANDARD PLANS A90A. (6) INSTALL CROSSWALK PER CALTRANS STANDARD PLANS A24F.

- (7) INSTALL WHITE ARROW LEGEND PER CALTRANS STANDARD PLAN A24A, TYPE I.
- $\langle 8 \rangle$  INSTALL STOP BAR PER CALTRANS STANDARD PLAN A24E. (9) INSTALL STOP LEGEND PER CALTRANS STANDARD PLAN A24D.

INSTALL 4-INCH WIDE WHITE STRIPING FOR PARKING STALLS.

INSTALL 4-INCH WIDE BLUE STRIPING PER CALTRANS STANDARD PLANS A90A.

INSTALL "NO PARKING" LEGEND PER CALTRANS STANDARD A24E. HATCH STRIPING SHALL NOT ENCROACH INTO "NO PARKING" LEGEND.

INSTALL BLUE PAINT ON CURB PER CALTRANS STANDARD PLANS A90B.

- 8 EXISTING P.C.C. PARKING LOT TO REMAIN.
- (7) EXISTING P.C.C. SPANDREL TO REMAIN.

- 6 EXISTING BUILDING TO REMAIN.

(3) EXISTING BARRIER CURB TO REMAIN.


(4) EXISTING CURB AND GUTTER TO REMAIN.

(5) EXISTING RIBBON GUTTER TO REMAIN.

STRIPING KEYNOTES

EXISTING KEYNOTES


1 EXISTING SIDEWALK TO REMAIN. (2) EXISTING DRIVEWAY TO REMAIN.



onool voodo id nin in	The Holt Group Engineering planning surveying	NO.	REVISIONS:
	201 E. HOBSONWAY         1601 N. IMPERIAL AVE.         36951 COOK STREET, STE. 103           BLYTHE, CA 92225         EL CENTRO, CA 92243         PALM DESERT, CA 92211           PHONE :         (760) 922-4658         PHONE :         (760) 337-3883           FAX :         (760) 922-4660         FAX :         (760) 337-5997		UNAUTHORIZED CHANGES & USES: The engineer preparing these plans will not be re for, or liable for, unauthorized changes to or uses of these plans. All changes to the plans must be in writing and must be approved by the preparer of these plans.

LOCATION: LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI) WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF HOBSONWAY, 26.8 METERS (88.0 FT) NORTH OF A BARBED WIRE RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK IS 2.35 METERS N FROM A WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57' VG DRAWN BY: VG ROBERT K. HOLT, P.E. CHECKED BY: responsible 09-01-2022 ins RKH DATE

	30 0 30 60 90 SCALE 1"= 30'	
	PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS IN THE CITY OF BLYTHE, CALIFORNIA	SHEET 9
<u>27943</u> R.C.E. NO.	SHEET CONTENT: STRIPING PLAN	9 of <u>14</u> sheets
03/31/24 REG. EXP.	LOCATION: BLYTHE, CA. CLIENT: PALO VERDE COLLEGE	JOB NO. 533.007



30	0	30	60	90
		SCALE 1"=	30'	

30	0	30	60	90

- $\langle 6 \rangle$  INSTALL CROSSWALK PER CALTRANS STANDARD PLANS A24F.

- (8) INSTALL STOP BAR PER CALTRANS STANDARD PLAN A24E.

INSTALL STOP LEGEND PER CALTRANS STANDARD PLAN A24D.

(7) INSTALL WHITE ARROW LEGEND PER CALTRANS STANDARD PLAN A24A, TYPE I.

5 INSTALL AN INTERNATIONAL SYMBOL OF ACCESSIBILITY (ISA) BLUE SYMBOL PER CALTRANS STANDARD A24C AND CALTRANS STANDARD PLANS A90A.

EXISTING KEYNOTES

1 EXISTING SIDEWALK TO REMAIN. (2) EXISTING DRIVEWAY TO REMAIN.

(6) EXISTING BUILDING TO REMAIN.

STRIPING KEYNOTES

(3) EXISTING BARRIER CURB TO REMAIN.

(4) EXISTING CURB AND GUTTER TO REMAIN.

(5) EXISTING RIBBON GUTTER TO REMAIN.

(7) EXISTING P.C.C. SPANDREL TO REMAIN.

8 EXISTING P.C.C. PARKING LOT TO REMAIN.


INSTALL 4-INCH WIDE WHITE STRIPING FOR PARKING STALLS.

INSTALL 4-INCH WIDE BLUE STRIPING PER CALTRANS STANDARD PLANS A90A.

INSTALL "NO PARKING" LEGEND PER CALTRANS STANDARD A24E. HATCH STRIPING SHALL NOT ENCROACH INTO "NO PARKING" LEGEND.

INSTALL BLUE PAINT ON CURB PER CALTRANS STANDARD PLANS A90B.

Carlo and and and and and and **REVISIONS**: The Holt Group ENGINEERING PLANNING SURVEYING UNAUTHORIZED CHANGES & USES: The engineer preparing these plans will not be responsible 1601 N. IMPERIAL AVE. EL CENTRO, CA 92243 PHONE : (760) 337-3883 FAX : (760) 337-5997 36951 COOK STREET, STE. 103 PALM DESERT, CA 92211 PHONE : (760) 427-8533 BLYTHE, CA 92225 PHONE : (760) 922-4658 FAX : (760) 922-4660 for, or liable for, unauthorized changes to or uses of these plans. All changes to the plans must be in writing and must be approved by the preparer of these plans.



	~ A	NSTALL "NO PARKING" LEGEND PER CALTRANS STANDARD A24E. HATCH STRIPING SHALL NOT ENCROACH INTO "NO PARKING" LEGEND.
•		NSTALL BLUE PAINT ON CURB PER CALTRANS STANDARD PLANS A90B.
	→ (I	NSTALL AN INTERNATIONAL SYMBOL OF ACCESSIBILITY ISA) BLUE SYMBOL PER CALTRANS STANDARD A24C AND CALTRANS STANDARD PLANS A90A.
	<b>6</b> ∕∎	NSTALL CROSSWALK PER CALTRANS STANDARD PLANS A24F.
•		NSTALL WHITE ARROW LEGEND PER CALTRANS STANDARD PLAN A24A, TYPE I.
•	11 <8	NSTALL STOP BAR PER CALTRANS STANDARD PLAN A24E.
•		NSTALL STOP LEGEND PER CALTRANS STANDARD PLAN A24D.

EXISTING KEYNOTES EXISTING SIDEWALK TO REMAIN.

(2) EXISTING DRIVEWAY TO REMAIN.

(6) EXISTING BUILDING TO REMAIN.

STRIPING KEYNOTES

③ EXISTING BARRIER CURB TO REMAIN.

(4) EXISTING CURB AND GUTTER TO REMAIN. (5) EXISTING RIBBON GUTTER TO REMAIN.

(7) EXISTING P.C.C. SPANDREL TO REMAIN.

(8) EXISTING P.C.C. PARKING LOT TO REMAIN.

INSTALL 4-INCH WIDE WHITE STRIPING FOR PARKING STALLS.

INSTALL 4-INCH WIDE BLUE STRIPING PER CALTRANS STANDARD PLANS A90A.

30	0	30	60	90
		SCALE 1"= 3	30'	

PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS IN THE CITY OF BLYTHE, CALIFORNIA SHEET CONTENT: 27943 R.C.E. NO. STRIPING PLAN 03/31/24 REG. EXP.

LOCATION: BLYTHE, CA.


SHEET								
10								
OF_	14	SHEETS						
JOB NO.								
533.007								

CLIENT: PALO VERDE COLLEGE

ഗ ш S

3

(3



				BE	NCHMARK	TABLE	
		Γ	TBM #	ELEVATION	DESCRIPTION		
			BM#1	391.69	BEGINING OF CU LOCATED AT EA ADA HANDICAP	JRB, TOP OF CURB STERLY CURB RADIUS OF PARKING SPACE	-
in the second se				30	0	30 60 SCALE 1"= 30'	90
				PARKING LO	RDE COLLEGE	NTS IA	SHEET
<u> </u>	27943 R.C.E. NO.	SHEET CO	NTENT		NG PLAN		<u>11</u> ог <u>14 sheets</u>
- –	03/31/24 REG. EXP.	LOCATION	: BL	YTHE, CA.	CLIENT:	PALO VERDE COLLEGE	ЈОВ NO. 533.007

- INSTALL STOP LEGEND PER CALTRANS STANDARD PLAN A24D.
- 5 INSTALL AN INTERNATIONAL SYMBOL OF ACCESSIBILITY (ISA) BLUE SYMBOL PER CALTRANS STANDARD A24C AND CALTRANS STANDARD PLANS A90A.

 $\langle 6 \rangle$  INSTALL CROSSWALK PER CALTRANS STANDARD PLANS A24F.

(8) INSTALL STOP BAR PER CALTRANS STANDARD PLAN A24E.

(7) INSTALL WHITE ARROW LEGEND PER CALTRANS STANDARD PLAN A24A, TYPE I.

- INSTALL "NO PARKING" LEGEND PER CALTRANS STANDARD A24E. HATCH STRIPING SHALL NOT ENCROACH INTO "NO PARKING" LEGEND. INSTALL BLUE PAINT ON CURB PER CALTRANS STANDARD PLANS A90B.
- INSTALL 4-INCH WIDE BLUE STRIPING PER CALTRANS STANDARD PLANS A90A.
- STALLS.
- STRIPING KEYNOTES 1 INSTALL 4-INCH WIDE WHITE STRIPING FOR PARKING
- (4) EXISTING CURB AND GUTTER TO REMAIN. (5) EXISTING RIBBON GUTTER TO REMAIN.

(7) EXISTING P.C.C. SPANDREL TO REMAIN.

8 EXISTING P.C.C. PARKING LOT TO REMAIN.

- (3) EXISTING BARRIER CURB TO REMAIN.
- (2) EXISTING DRIVEWAY TO REMAIN.


(6) EXISTING BUILDING TO REMAIN.

- EXISTING KEYNOTES 1 EXISTING SIDEWALK TO REMAIN.



			ELEVATION: <u>EL= 391.57'</u> LOCATION:	BROFESS/OV	PREPARED UNDER THE DIRECT SUPERVISION C	λ.	PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS	SHEET
			SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI) WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM	SEOSERT K. HAR	Color L. HOH		IN THE CITY OF BLYTHE, CALIFORNIA SHEET CONTENT:	12
		VG	THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF HORSONIWAY 26 METERS (89.0 ET) NORTH OF A BARBED WIDE	С 27943 П Ехр. 03-81-24 +	ROBERT K. HOLT, P.E.	27943 R.C.E. NO.	A.C. GRINDING	of <u>14</u> sheets
UTHORIZED CHANGES & USES: The engineer preparing these plans will not be responsible br liable for, unauthorized changes to or uses of these plans. All changes to the plans		CHECKED BY:	RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK	OF THE OF CALIFORN	09-01-2022	03/31/24		JOB NO. 533.007
or lia	HORIZED CHANGES & USES: The engineer preparing these plans will not be responsible able for, unauthorized changes to or uses of these plans. All changes to the plans in writing and must be approved by the preparer of these plans.	able for, unauthorized changes to or uses of these plans. All changes to the plans	HORIZED CHANGES & USES: The engineer preparing these plans will not be responsible CHECKED BY: able for, unauthorized changes to or uses of these plans. All changes to the plans	DRAWN BY:       URAWN BY:         VG       VG         HORIZED CHANGES & USES: The engineer preparing these plans will not be responsible       CHECKED BY:         Bable for, unauthorized changes to or uses of these plans. All changes to the plans       All changes to the plans	DRAWN BY:       DRAWN BY:         VG       VG         HORIZED CHANGES & USES: The engineer preparing these plans will not be responsible able for, unauthorized changes to or uses of these plans. All changes to the plans       CHECKED BY:         DKL       DKL	DRAWN BY:       DRAWN BY:         VG       VG         HORIZED CHANGES & USES: The engineer preparing these plans will not be responsible       CHECKED BY:         DKH       DKH	DRAWN BY:       DRAWN BY:       WEST FROM Chyperplane       DRAWN BY:       DRAWN BY:       West From Chyperplane       DRAWN BY:       West From Chyperplane       DRAWN BY:       West From Chyperplane       DRAWN BY:       DRAWN BY: </td <td>DRAWN BY:       DRAWN BY:</td>	DRAWN BY:       DRAWN BY:

- $\langle \underline{\textbf{7}} \rangle$  INSTALL HANDICAP RAMP PER CALTRANS STANDARD PLAN A88A.
- (8) INSTALL 3-INCHES OF THE PARKING LOT A.C. GRINDINGS AS ILLUSTRATED ON SHEET 12 OF THE IMPROVEMENTS PLANS. COMPACT A.C. GRINDINGS MATERIAL TO 90 PERCENT MAXIMUM DENSITY PER ASTM D-1557.



### SPECIFICATIONS FOR UNDERGROUND CONDUIT PLACEMENT WITHIN THE CITY OF BLYTHE

CABLE MARKING RIBBON. CABLE MARKING RIBBON SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR. THE CABLE MARKING RIBBON SHALL BE INSTALLED ABOVE ALL DIRECT- BURIED CABLE AND DIRECT-BURIED CONDUIT. THE RIBBON SHALL BE PLACED AT A DEPTH OF 6- INCHES BELOW SUB-GRADE AND DIRECTLY *ABOVE* THE CABLE OR CONDUIT. THE TAPE SHALL BE UNAFFECTED BY SOIL ACIDS OR ALKALIS.

CROSSING UNDERGROUND STRUCTURES. WHERE THE TOP OF THE UNDERGROUND PIPE OR STRUCTURE IS 4 FEET BELOW GRADE OR DEEPER. THE CABLE MAY PASS OVER THE STRUCTURE. IN CASES WHERE THE CONDUIT PASSES ABOVE OR BELOW AN UNDERGROUND OBSTRUCTION SUCH AS A UTILITY LINE, A MINIMUM CLEARANCE OF 6 INCHES SHALL BE MAINTAINED WITH 12-INCH CLEARANCE TYPICAL

RESTORATION OF THE RIGHT OF-WAY. THE RIGHT-OF-WAY SHALL BE RESTORED AS FAR AS PRACTICAL TO THE ORIGINAL CONDITION. SLOPE PROTECTION AND EROSION CONTROL SHALL BE IN ACCORDANCE WITH THE SECTION ENTITLED EXCAVATION AND TRENCHING. OPEN TRENCHES OR PITS SHALL BE BACKFILLED IMMEDIATELY AFTER THE CABLE IS INSTALLED.

UNDERGROUND CONDUIT CROSSINGS. WHERE CONDUITS ARE REQUIRED UNDER STREETS, RAILROADS OR OTHER STRUCTURES, THE CONDUITS SHALL BE TRENCHED, JACKED OR OTHERWISE FORCED UNDERNEATH THE STREET, RAILROAD OR OTHER STRUCTURE OR THE CONDUIT MAY BE INSTALLED IN A CASING.

THE CASING PIPE SHALL BE INSTALLED USING JACKING EQUIPMENT THAT ENCASES THE HOLE AS THE EARTH IS REMOVED THROUGH THE INTERIOR OF THE CASING. BORING WITHOUT THE CONCURRENT INSTALLATION OF THE CASING PIPE WILL NOT BE PERMITTED. THE INSTALLATION SHALL BE PERFORMED IN A MANNER THAT WILL NOT DISRUPT TRAFFIC NOR DAMAGE THE SUBGRADE, AND THAT WILL PROVIDE ACCURATE ALIGNMENT AND GRADE OF THE PIPE. THERE SHALL BE NO SPACE BETWEEN THE EARTH AND THE OUTSIDE OF THE CASING PIPE.

BEFORE STARTING WORK ON THE CROSSING, THE CONTRACTOR SHALL SUBMIT COMPLETE DETAILS OF HIS PROPOSED METHODS, MATERIALS AND TIME SCHEDULE TO THE CITY OF BLYTHE DEPARTMENT WORKS. WORK SHALL NOT BEGIN ON THE CROSSING UNTIL WRITTEN NOTIFICATION TO PROCEED HAS BEEN OBTAINED. FROM THE CITY OF BLYTHE DEPARTMENT WORKS.

MANHOLES. SHALL BE OF TRAFFIC GRADE QUALITY AS APPROVED BY THE CITY.

EXCAVATION AND TRENCHING

SHEETING AND SHORING. THE STABILITY OF PREVIOUSLY CONSTRUCTED STRUCTURES AND FACILITIES SHALL NOT BE IMPAIRED OR ENDANGERED BY EXCAVATION OR TRENCHING WORK. PREVIOUSLY CONSTRUCTED STRUCTURES AND FACILITIES INCLUDE BOTH STRUCTURES AND FACILITIES EXISTING WHEN THIS CONSTRUCTION BEGAN AND STRUCTURES AND FACILITIES ALREADY PROVIDED UNDER THESE SPECIFICATIONS.

ADEQUATE SHEETING AND SHORING SHALL BE PROVIDED AS REQUIRED TO PROTECT AND MAINTAIN THE STABILITY OF PREVIOUSLY CONSTRUCTED STRUCTURES AND FACILITIES AND THE SIDES OF EXCAVATIONS AND TRENCHES UNTIL THEY ARE BACKFILLED. SHEETING, BRACING AND SHORING SHALL BE DESIGNED AND BUILT TO WITHSTAND ALL LOADS THAT MIGHT BE CAUSED BY EARTH MOVEMENT OR PRESSURE, AND SHALL MAINTAIN THE SHAPE OF THE EXCAVATION UNDER ALL CIRCUMSTANCES.

REMOVAL OF WATER. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN ADEQUATE DEWATERING EQUIPMENT TO REMOVE AND DISPOSE OF ALL SURFACE AND GROUND WATER ENTERING EXCAVATIONS, TRENCHES AND OTHER PARTS OF THE WORK. EACH EXCAVATION OR TRENCH SHALL BE KEPT DRY DURING SUBGRADE PREPARATION AND CONTINUALLY THEREAFTER UNTIL THE CONSTRUCTION TO BE PROVIDED THEREIN IS COMPLETED TO THE EXTENT THAT NO DAMAGE FROM HYDROSTATIC PRESSURE, FLOTATION OR OTHER CAUSE WILL RESULT.

SURFACE WATER SHALL BE DIVERTED OR OTHERWISE PREVENTED FROM ENTERING EXCAVATED AREAS OR TRENCHES TO THE GREATEST EXTENT PRACTICABLE WITHOUT CAUSING DAMAGE TO ADJACENT PROPERTY. THE METHOD OF DISPOSAL SHALL BE APPROVED BY THE CITY.

EXCAVATIONS OVER 8 FEET IN DEPTH FROM EXISTING GRADE ELEVATIONS BETWEEN THE COLORADO RIVER AND RANNELS DRAIN (WEST OF BLYTHE). ARE LIKELY TO BE BELOW THE EXISTING WATER TABLE IN THE VALLEY. SOIL IN THIS AREA IS VERY PERMEABLE AND UNSTABLE AND EXCAVATIONS WILL REQUIRE STABILIZATION AND EXTENSIVE DEWATERING PROCEDURES.

MAINTENANCE OF TRAFFIC: THE CONTRACTOR SHALL CONTACT THE LOCAL AUTHORITY HAVING JURISDICTION OVER TRAFFIC CONTROL AND FOLLOW ANY RULES OR REGULATIONS SET FORTH. IN GENERAL, WHENEVER IT IS NECESSARY TO CROSS, OBSTRUCT OR CLOSE ROADS, DRIVEWAYS, PARKING AREAS, AND WALKS, THE CONTRACTOR SHALL PROVIDE AND MAINTAIN SUITABLE AND SAFE BRIDGES, DETOURS OR OTHER TEMPORARY EXPEDIENTS AT HIS OWN EXPENSE. IN MAKING OPEN CUT ROAD CROSSINGS, THE CONTRACTOR SHALL NOT BLOCK MORE THAN ONE-HALF OF THE ROAD AT ANY TIME AND PROVIDE FOR TWO-WAY TRAFFIC.

THE CONTRACTOR SHALL PROVIDE A "TRAFFIC CONTROL AND WORKER PROTECTION PLAN", PREPARED IN ACCORDANCE WITH CALTRANS DIVISION OF MAINTENANCE -CHAPTER 8 (PROTECTION OF WORKERS), WHEN WORKING IN A DEDICATED RIGHT-OF-WAY (R/W). THE 'PLAN' SHALL BE SUBMITTED TO AND BE APPROVED BY THE CITY OF BLYTHE-DEPARTMENT OF PUBLIC WORKS SEVEN (7) DAYS PRIOR TO ANY WORK IN THE R/W. THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGMEN OR OTHER DEVICES NECESSARY TO PROVIDE FOR WORKER AND PUBLIC SAFETY. ALL TRAFFIC CONTROL AND SAFETY DEVICES MUST BE ONSITE, INSPECTED AND APPROVED PRIOR TO THE COMMENCEMENT OF ANY WORK. THE CONTRACTOR SHALL KEEP ALL CONTROL AND SAFETY DEVICES IN PROPER POSITION AND WORKING ORDER AT ALL TIMES.

WHERE REQUIRED BY THE DRAWINGS, THE CONTRACTOR SHALL WIDEN THE SHOULDER ON THE OPPOSITE SIDE OF THE ROAD TO FACILITATE TRAFFIC FLOW WHILE BLOCKING HALF OF A ROAD WITH AN OPEN CUT. TEMPORARY CRUSHED ROCK SURFACING SHALL BE PROVIDED AS NECESSARY ON THE WIDENED SHOULDERS.

PROTECTION OF UNDERGROUND CONSTRUCTION. THE CONTRACTOR SHALL LOCATE, PROTECT, SHORE, BRACE, SUPPORT AND MAINTAIN ALL EXISTING UNDERGROUND PIPES, CONDUITS, DRAINS AND OTHER UNDERGROUND CONSTRUCTION THAT MAY BE UNCOVERED OR OTHERWISE AFFECTED BY THE WORK.

PRESERVATION OF TREES AND NATIVE PLANTS. TREES AND NATIVE PLANTS SHALL BE PRESERVED AND PROTECTED AS MUCH AS POSSIBLE. UNLESS SPECIFICALLY AUTHORIZED BY THE CITY, TREES AND NATIVE PLANTS SHALL BE REMOVED FROM ONLY THOSE AREAS, WHICH WILL BE EXCAVATED, FILLED OR BUILT UPON. CONSIDERATION WILL BE GIVEN TO THE REMOVAL OF ADDITIONAL TREES ONLY WHERE ESSENTIAL, IN THE OPINION OF THE ENGINEER, FOR THE EFFECTIVE EXECUTION OF THE WORK.

TREES AND NATIVE PLANTS LEFT STANDING SHALL BE ADEQUATELY PROTECTED FROM PERMANENT DAMAGE BY CONSTRUCTION OPERATIONS.

STABILIZATION. SUBGRADES FOR STRUCTURES AND THE BOTTOM OF TRENCHES SHALL BE FIRM, DENSE AND THOROUGHLY COMPACTED AND CONSOLIDATED; SHALL BE FREE FROM EXCESS MOISTURE AND SHALL BE SUFFICIENTLY STABLE TO REMAIN FIRM AND INTACT UNDER THE FEET OF THE WORKMEN.

SUBGRADES FOR STRUCTURES AND TRENCH BOTTOMS WHICH ARE OTHERWISE SOLID BUT WHICH BECOME MUCKY ON TOP DUE TO CONSTRUCTION OPERATIONS SHALL BE REINFORCED WITH ONE OR MORE LAYERS OF CRUSHED ROCK OR GRAVEL.

ALL STABILIZATION WORK SHALL BE PERFORMED BY AND AT THE EXPENSE OF THE CONTRACTOR.

TESTING. THE CONTRACTOR SHALL PROVIDE ALL FIELD AND LABORATORY TESTING REQUIRED TO DETERMINE COMPLIANCE WITH THE REQUIREMENTS OF THIS SECTION.

ALL LABORATORY TESTING SHALL BE DONE BY AN INDEPENDENT TESTING LABORATORY ACCEPTABLE TO THE CITY AND RETAINED AND PAID BY THE CONTRACTOR. FIELD SAMPLING SHALL BE DONE BY THE TESTING LABORATORY.

FIELD-TESTING SHALL BE PERFORMED BY THE CONTRACTOR AT LOCATIONS SELECTED BY THE CITY TO DETERMINE IF THE MATERIALS AND CONSTRUCTION WILL MEET THE REQUIREMENTS OF THE SPECIFICATIONS.

COMPACTION TESTS FOR ENCROACHMENTS PARALLEL TO AND WITHIN A ROAD RIGHT-OF-WAY SHALL BE MADE AT A MINIMUM OF THREE PER BLOCK OR AT 200 FOOT CENTERS, WHICHEVER IS LESS.

A MINIMUM OF TWO COMPACTION TESTS SHALL BE PERFORMED AT EACH TRENCH CROSSING AT A ROAD.

MAXIMUM DENSITY FOR COHESIVE COMPACTED MATERIALS SHALL BE DETERMINED IN ACCORDANCE WITH ASTM D 1557-91. THE TERMS "MAXIMUM DENSITY" AND "OPTIMUM MOISTURE CONTENT" SHALL BE AS DEFINED IN ASTM D 1557-91 MODIFIED BY USING THREE LAYERS INSTEAD OF FIVE LAYERS TO OBTAIN A COMPACTIVE EFFORT OF 33,750 FULBS. PER CU. FT. FIELD DENSITY OF SOIL SHALL BE DETERMINED BY ASTM METHOD 1556-64T.

A COPY OR EACH TEST RESULT SHALL BE PROMPTLY FURNISHED TO THE CITY.

STRUCTURE EXCAVATION FOR STRUCTURES SHALL BE DONE TO LINES AND ELEVATIONS INDICATED ON THE DRAWINGS AND TO THE LIMITS REQUIRED TO PERFORM THE CONSTRUCTION WORK. MACHINE EXCAVATION SHALL BE CONTROLLED TO PREVENT UNDERCUTTING THE PROPER SUBGRADE ELEVATIONS AND SHALL NOT BE USED WITHIN 3 FEET OF PERMANEN STRUCTURES AND FACILITIES. ONLY HAND TOOLS SHALL BE USED FOR EXCAVATION AROUND PERMANENT STRUCTURES, FACILITIES AND UNDERGROUND UTILITIES.

PRIOR TO ANY CONSTRUCTION INVOLVING JACKING OR BORING A PIPE CONDUIT BELOW A RAILROAD, CANAL, DRAIN, ROAD OR OTHER STRUCTURE, THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTHS OF THE STRUCTURE AND ANY UTILITIES ADJACENT OR TRANSVERSE TO THE JACKING OPERATION. UTILITIES SHALL BE EXPOSED TO THE GREATEST EXTENT POSSIBLE PRIOR TO THE JACKING OPERATION.

WORK SHALL BE DONE SO THE CONSTRUCTION AREAS WILL BE AS FREE AS POSSIBLE FROM OBSTRUCTIONS AND FROM INTERFERENCE WITH THE TRANSPORTATION, STORAGE OR HANDLING OF MATERIALS. EXCAVATED MATERIALS FREE OF TRASH, ROCKS, ROOTS AND OTHER FOREIGN MATERIALS, AND WHICH MEET THE SPECIFIED REQUIREMENTS, MAY BE USED AS REQUIRED FOR THE BACKFILLS CONSTRUCTED UNDER THESE SPECIFICATIONS.

VERTICAL FACES OF EXCAVATIONS SHALL NOT BE UNDERCUT TO PROVIDE FOR EXTENDED FOOTINGS

DRAINAGE FILTER MATERIAL SHALL BE PLACED WHERE REQUIRED BY THE CITY AND SHALL BE COMPACTED TO A DEGREE THAT WILL PERMIT WATER TO PASS IT READILY, BUT WILL NOT HAVE EXCESSIVE SETTLEMENT LATER.

CONCRETE ENCASED PVC CONDUIT TRENCHING. TRENCHES FOR CONCRETE ENCASED PVC CONDUIT SHALL BE DUG TO LINES INDICATED ON THE DRAWINGS OR AT OTHER LOCATIONS ACCEPTABLE TO THE CITY AND TO THE EXACT DEPTH REQUIRED FOR THE PROPER GRADE OF THE CONDUITS WITH ENCASEMENT OR EMBEDMENT. WHEREVER POSSIBLE, THE TRENCHES SHALL BE EXCAVATED TO PERMIT THE CONCRETE ENCASED PVC CONDUIT TO REST ON UNDISTURBED EARTH OR ROCK. WHERE IT IS NECESSARY TO TRENCH THROUGH BACKFILL, THE EARTH SHALL BE WELL COMPACTED BEFORE THE CONCRETE ENCASED PVC CONDUIT IS INSTALLED.

ALL TRENCHES SHALL BE WIDE ENOUGH TO PROVIDE AMPLE ROOM FOR WORKMEN ENGAGED IN HANDLING AND INSTALLING CONDUITS. WHERE IT IS NECESSARY TO REDUCE THE EARTH LOAD ON TRENCH BANKS TO PREVENT SLIDING OR CAVING, TRENCH BANKS MAY BE CUT BACK ON SLOPES, WHICH SHALL NOT EXTEND LOWER THAN 12-INCHES ABOVE THE TOP OF THE CONCRETE ENCASED PVC CONDUIT.

he Holt Group	REVISIONS: APPROVED DATE	DESIGN BY: VG	ELEVATION: <u>EL= 391.57'</u> LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT	ED PROFESSION	PREPARED UNDER THE DIRECT SUPERVISION OF:		PALO VERDE COLLEGE PARKING LOT IMPROVEMENTS IN THE CITY OF BLYTHE, CALIFORNIA		SHEET
EERING PLANNING SURVEYING		DRAWN BY: VG	STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI) WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT) SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF HOBSONWAY 26 8 METERS (88.0 FT) NORTH OF A BARBED WIRF	ехр. 03-81-24 *	ROBERT K. HOLT, P.E.	27943 R.C.E. NO.	SHEET CONTENT: SPECIFICATIONS		OF_ <b>14</b> SHEETS
2223 EL CENTRO, CA 92243 PHONE: (760) 337-3883 PHONE: (760) 427-8533 for, or liable	RIZED CHANGES & USES: The engineer preparing these plans will not be responsible e for, unauthorized changes to or uses of these plans. All changes to the plans writing and must be approved by the preparer of these plans.	CHECKED BY:	RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK IS 2.35 METERS N FROM A WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57'	OF THE OF CALIFORN		03/31/24 REG. EXP.	LOCATION: BLYTHE, CA. CLIENT: PAL	.0 VERDE COLLEGE	JOB NO. 533.007

SUBGRADE SOIL SHALL BE FIRM AND COMPACT. SHOULD THE TOPSOIL IN ANY AREA BE MUCKY OR, SHOULD IT WORK INTO MUD UNDER THE FEET OF THE WORKMEN, THE CONTRACTOR SHALL REINFORCE IT. REINFORCING SHALL BE DONE BY REMOVING A SUFFICIENT DEPTH OF MUCKY MATERIAL AND REPLACING IT BY ONE OR MORE THIN LAYERS OF CRUSHED ROCK OR GRAVEL, EACH LAYER BEING TIGHTLY ROLLED OR OTHERWISE EMBEDDED IN THE SOIL. THE SUBGRADE SHALL THEN BE BROUGHT TO THE PROPER LEVEL BY MEANS OF A THIN LAYER OF SAND TAMPED OR ROLLED INTO THE REINFORCED SUBSOIL. NO CONDUIT SHALL BE LAID UNDER UNSUITABLE WEATHER OR TRENCH CONDITIONS.

IF ROCK IS ENCOUNTERED IN THE EXCAVATION, IT SHALL BE REMOVED AND REPLACED WITH A SUITABLE TAMPED OR ROLLED GRANULAR MATERIAL AND BROUGHT TO THE PROPER LAYING ELEVATION AS DESCRIBED ABOVE.

BACKFILL FOR TRENCHES. ALL BACKFILL FOR TRENCHES OPENED TO PLACE CABLE OR CONDUIT SHALL BE COMPACTED. BACKFILL MATERIAL SHALL BE EITHER SUITABLE JOB EXCAVATED MATERIAL OR SUITABLE MATERIAL FURNISHED BY THE CONTRACTOR AND AS DESCRIBED AS FOLLOWS:

COMPACTED BACKFILL MATERIAL UNDER ROAD SURFACES, ROAD SHOULDERS, PARKING AREAS AND LAWN AREAS SHALL BE FINELY DIVIDED AND FREE FROM DEBRIS, ORGANIC MATERIAL AND STONES LARGER THAN 3-INCHES IN GREATEST DIMENSION. COMPACTED BACKFILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT EXCEEDING 8-INCHES IN UNCOMPACTED THICKNESS. INCREASED LAYER THICKNESS MAY BE PERMITTED FOR NONCOHESIVE MATERIAL IF THE CONTRACTOR DEMONSTRATES TO THE SATISFACTION OF THE CITY THAT THE SPECIFIED COMPACTED DENSITY WILL BE OBTAINED. THE METHOD OF COMPACTION AND THE EQUIPMENT USED SHALL BE APPROPRIATE FOR THE MATERIAL TO BE COMPACTED AND SHALL NOT TRANSMIT DAMAGING SHOCKS TO THE CONDUIT.

TRENCHING ACROSS OR WITHIN CITY OF BLYTHE STREET R/W SHALL BE BACKFILLED USING CLASS II BASE (AS DESCRIBED IN THE JULY, 1995 EDITION OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATION SECTION 25).

SPECIFIC BACKFILL GRADATION REQUIREMENTS ARE AS FOLLOWS:

100 PER CENT PASSING 3" SIEVE 90-100 PER CENT PASSING 2" SIEVE 40-90 PERCENT PASSING NO. 4 SIEVE 0-25 PERCENT PASSING NO. 200 SIEVE SAND EQUIVALENT MUST BE 21 MIN.

NO NATIVE SOIL REMOVED FROM TRENCHES SHALL BE USED FOR BACKFILL PURPOSES WITHOUT APPROVAL OF CITY OF BLYTHE DIRECTOR OF PUBLIC WORKS. BACKFILL SHALL BE COMPACTED TO 90 PER CENT OF MAXIMUM DENSITY. FOUR INCHES OF HOT MIXED ASPHALTIC CONCRETE SHALL BE PLACED ON ALL TRENCHES ACROSS PAVED AREAS IN ACCORDANCE WITH THE FOLLOWING SECTION.

PAVEMENT REMOVAL AND REPLACEMENT. CUTS IN CONCRETE AND ASPHALT PAVED SHOULDERS SHALL BE NO LARGER THAN NECESSARY TO PROVIDE WORKING SPACE. CUTTING SHALL BE STARTED WITH A CONCRETE SAW THAT WILL PROVIDE A CLEAN GROOVE AT LEAST 2-1/2 INCHES DEEP ALONG EACH SIDE OF THE TRENCH.

CONCRETE AND ASPHALT PAVEMENT OVER AND ADJACENT TO TRENCHES EXCAVATED SHALL BE REMOVED SO THAT A SHOULDER NOT LESS THAN 1 FOOT IN WIDTH AT ANY POINT IS LEFT BETWEEN THE CUT EDGE OF THE PAVEMENT AND THE TOP EDGE OF THE TRENCH. TRENCH WIDTH AT THE BOTTOM SHALL NOT BE GREATER THAN AT THE TOP AND NO UNDERCUTTING WILL BE PERMITTED.

PAVEMENT CUTS SHALL BE MADE TO AND BETWEEN STRAIGHT OR ACCURATELY MARKED CURVED LINES, WHICH, UNLESS OTHERWISE REQUIRED. SHALL BE PARALLEL TO THE CENTERLINE OF THE PAVEMENT.

IF THE TRENCH PARALLELS THE LENGTH OF CONCRETE WALKS AND THE TRENCH LOCATION IS ALL OR PARTIALLY UNDER THE WALK, THE ENTIRE WALK SHALL BE REMOVED AND REPLACED. WHERE THE TRENCH CROSSES DRIVES, WALKS, CURBS OR OTHER SURFACE CONSTRUCTION, THE SURFACE CONSTRUCTION SHALL BE REMOVED AND REPLACED BETWEEN EXISTING JOINTS, OR BETWEEN SAW CUTS AS SPECIFIED FOR PAVEMENT. STREET SPECIFICATIONS FOR CONSTRUCTION IN THE CITY OF BLYTHE ARE INDICATED AT THE END OF THIS SECTION.

CUT OR DAMAGED SURFACES DUE TO CONSTRUCTION SHALL BE REPLACED WITH NEW SURFACING. REPLACEMENT SURFACING SHALL MATCH EXISTING SURFACING AND SHALL BE FINISHED FLUSH WITH EXISTING ADJOINING SURFACES. PAVEMENT REPLACEMENT MATERIALS SHALL MATCH THE THICKNESS AND DENSITY OF THE MATERIAL EXCAVATED UNLESS OTHERWISE SPECIFIED HEREINAFTER. AS A MINIMUM, THE FOLLOWING REQUIREMENTS SHALL BE MET.

1. COMPACTED SUBGRADE SHALL MEET THE REQUIREMENTS OF BACKFILL FOR TRENCHES.

2. BACKFILL AND BASE COARSE MATERIAL SHALL BE AS STATED IN BACKFILL FOR TRENCHES UNLESS OTHERWISE SPECIFICALLY APPROVED BY THE CITY.

TWO COURSE BITUMINOUS SURFACE TREATMENTS SHALL COMPLY WITH THE APPLICABLE SECTIONS OF THE CALTRANS STANDARDS.

4. ASPHALT CONCRETE PAVING SHALL COMPLY WITH THE APPLICABLE SECTIONS OF THE CALTRANS STANDARDS. ASPHALT CONCRETE SHALL BE A JOB MIX FORMULA WITH A DESIGN DENSITY BETWEEN 95 AND 97 PER CENT OF VOIDLESS MIXTURE DETERMINED BY THE 50 BLOW MARSHALL TEST, IN ACCORDANCE WITH THE STATE OF CALIFORNIA CALTRANS STANDARD SPECIFICATION, CURRENT EDITION. HOT, PLANT MIXED MATERIAL SHALL BE OF THE SIZE, 3/4" MEDIUM-MAXIMUM TO 3/8" MAX. TYPE A, B, OR OPEN GRADED AGGREGATE BLENDED WITH EITHER AR4000, OR ARS000 STEAM REFINED PAVING ASPHALTS, AS DEFINED IN SECTION 92, "ASPHALTS" AND SECTION 39 "ASPHALT CONCRETE". REQUIREMENTS FOR ASPHALT CONCRETE PAVING SHALL BE AS SPECIFIED UNLESS OTHERWISE SPECIFICALLY APPROVED BY THE CITY OR AS STATED BELOW.

- A. ASPHALTIC CONCRETE REPLACED IN THE CITY OF BLYTHE STREET RIGHT-OF-WAY SHALL BE A MINIMUM OF 3 INCHES THICK WITH 3/4 INCH MAXIMUM AGGREGATE SIZE. GREATER THICKNESSES OF ASPHALTIC CONCRETE AND /OR CLASS II BASE MATERIAL MAY BE REQUIRED AS DETERMINED BY THE GEOTECHNICAL INVESTIGATION.
- B. TEMPORARY REPAVING USING COLD MIX ASPHALTIC CONCRETE WILL BE ALLOWED FOR A MAXIMUM OF 30 DAYS FROM DATE OF TRENCHING.
- c. PAVEMENT REPLACEMENT SHALL MATCH EXISTING PAVING IN TYPE OF PAVEMENT, APPEARANCE, WEARING SURFACE AND DURABILITY TO THE MAXIMUM EXTENT PRACTICAL. PAVEMENT REPAIR SHALL BE SUBJECT TO APPROVAL BY THE CITY. PAVEMENT REPAIR NOT INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THESE SPECIFICATIONS SHALL BE REMOVED AND REPLACED. CONCRETE PAVING SHALL COMPLY WITH THE APPLICABLE SECTIONS OF THE CALTRANS STANDARDS. CONCRETE REQUIREMENTS SHALL BE IN ACCORDANCE WITH THE SECTION ENTITLED CAST-IN-PLACE CONCRETE. REPLACEMENT SHALL MATCH EXISTING STRUCTURES TO THE MAXIMUM EXTENT PRACTICAL AND SHALL INCLUDE CURBING, WALKWAYS OR ANY OTHER CONCRETE

STRUCTURE DAMAGED DURING CONSTRUCTION.

MAINTENANCE AND RESTORATION OF BACKFILL. BACKFILL THAT SETTLES OR ERODES BEFORE FINAL ACCEPTANCE OF THE WORK, AND PAVEMENT STRUCTURES AND OTHER FACILITIES DAMAGED BY SUCH SETTLEMENT OR EROSION SHALL BE REPAIRED. THE SETTLED OR ERODED AREAS SHALL BE REFILLED, COMPACTED AND GRADED TO CONFORM TO THE ELEVATION INDICATED ON THE DRAWINGS OR TO THE ELEVATION OF THE ADJACENT GROUND SURFACE. DAMAGED FACILITIES SHALL BE REPAIRED IN A MANNER ACCEPTABLE TO THE CITY. THE CONTRACTOR WILL GUARANTEE HIS PAVEMENT REPAIRS FOR ONE YEAR.

DISPOSITION OF MATERIALS. EXCAVATED EARTH MATERIALS SHALL BE USED TO CONSTRUCT BACKFILLS TO THE EXTENT REQUIRED. SURPLUS EARTH, IF ANY, AND MATERIALS WHICH ARE NOT SUITABLE FOR BACKFILL SHALL BE SPOILED IN A MANNER AND LOCATION AS APPROVED BY THE CITY.

### SPECIFICATION FOR THE PLACEMENT OF CAST-IN-PLACE CONCRETE

PRELIMINARY REVIEW. THE SOURCE AND QUALITY OF CONCRETE MATERIALS AND THE CONCRETE PROPORTIONS PROPOSED FOR THE WORK SHALL BE SUBMITTED TO THE CITY FOR REVIEW BEFORE THE CONCRETE WORK IS STARTED. SUCH REVIEW WILL BE FOR GENERAL ACCEPTABILITY ONLY AND CONTINUED COMPLIANCE WITH ALL CONTRACT PROVISIONS WILL BE REQUIRED.

LIMITING REQUIREMENTS. CONCRETE UTILIZED FOR BUT NOT LIMITED TO CURB AND GUTTER, SPANDRELS, SIDEWALKS, CURB RETURNS, MANHOLE BASES, RINGS FOR MANHOLE FRAMES, AND VALVE RISERS AND RINGS FOR WATER RISERS, SHALL BE TYPE V CEMENT, CLASS 3 CONCRETE AND SHALL HAVE 1.5 LBS. OF POLYPROPYLENE FIBER PER CUBIC YARD OF CONCRETE. POLYPROPYLENE FIBER SHALL BE "FIBER MESH" OR AN APPROVED EQUAL. THE QUANTITY OF PORTLAND CEMENT EXPRESSED IN POUNDS PER CUBIC YARD, SHALL BE NOT LESS THAN THAT INDICATED IN THE FOLLOWING TABLE. THESE MINIMUM CEMENT FACTORS SHALL APPLY ONLY TO CONCRETE CONTAINING EITHER THE SPECIFIED PLASTICIZER OR PLASTICIZING RETARDER. IF, FOR ANY REASON, BOTH THE PLASTICIZER AND PLASTICIZING

RETARDER ARE OMITTED, THE CEMENT FACTOR SHALL BE INCREASED BY 10 PER CENT.

2/4"

COURSE AGGREGATE SIZE	
FROM NO. 4 SIEVE TO	
CONCRETE SLUMP	

CONCRETE SLUMP			3/4	
3 INCHES	592	564	536	
4 INCHES	611	583	555	
5 INCHES	630	602	573	

TOTAL WATER CONTENT	NOT MORE THAN 6.4 GALLONS PER 100 POUNDS OF CEMENT
COARSE AGGREGATE SIZE	ONE INCH TO NO. 4
TOTAL AIR CONTENT	5 PERCENT PLUS OR MINUS 1 PERCENT
CONSISTENCY	WORKABLE, WITHOUT SEGREGATION, WITH SLUMP NOT MORE THAN 4 INCHES WHEN CONCRETE IS PLACED
MIXING	THOROUGHLY IN A MECHANICAL MIXER FOR NOT LESS THAN 3 MINUTES

COMPRESSIVE STRENGTH NOT LESS THAN 2500 PSI AT AGE 28 DAYS

BATCHING AND MIXING. BATCHING AND MIXING SHALL CONFORM TO ASTM C94, EXCEPT AS OTHERWISE SPECIFIED HEREIN.

TRUCK MIXERS SHALL BE REVOLVING DRUM TYPE AND SHALL BE EQUIPPED WITH A MIXING WATER TANK. ONLY THE PRESCRIBED AMOUNT OF MIXING WATER SHALL BE PLACED IN THE TANK FOR ANY ONE BATCH UNLESS THE TANK IS EQUIPPED WITH A DEVICE BY WHICH THE AMOUNT OF WATER

ADDED TO EACH BATCH CAN BE READILY VERIFIED BY THE CITY. A DELIVERY TICKET SHALL BE PREPARED FOR EACH LOAD OF READY-MIXED CONCRETE DELIVERED AND HANDED TO THE CITY BY THE TRUCK OPERATOR AT THE TIME OF DELIVERY. TICKETS SHALL SHOW THE NUMBER OF YARDS DELIVERED THE QUANTITIES OF EACH MATERIAL IN THE BATCH, THE OUTDOOR TEMPERATURE IN THE SHADE, AND THE TIME AT WHICH THE CEMENT WAS ADDED.

SLUMP. A SLUMP TEST SHALL BE MADE EACH DAY CONCRETE IS PLACED. SLUMP SHALL BE DETERMINED IN ACCORDANCE WITH ASTM C143.

ASTM C231.

28 DAYS.

TEST REPORTS. THE CONTRACTOR SHALL FURNISH THE CITY CERTIFIED REPORTS OF ALL TESTS MADE BY THE TESTING LABORATORY.

REPAIRING DEFECTIVE CONCRETE. DEFECTS IN FORMED CONCRETE SURFACES SHALL BE REPAIRED TO THE SATISFACTION OF THE CITY WITHIN 24 HOURS AND DEFECTIVE CONCRETE SHALL BE REPLACED WITHIN 48 HOURS AFTER THE ADJACENT FORMS HAVE BEEN REMOVED. ALL CONCRETE WHICH IS POROUS, HONEYCOMBED AND OTHERWISE DEFECTIVE TO A DEPTH IN EXCESS OF ONE INCH, SHALL BE CUT OUT AND REMOVED.

THE CONTRACTOR IS RESPONSIBLE TO PREVENT VANDALISM OR GRAFFITI TO FRESH CONCRETE. DRY SACK OR OTHER REPAIR WILL NOT BE ALLOWED. REMOVE AND REPLACE ONLY. ANYTHING OFFENSIVE TO THE PUBLIC SHALL BE REPLACED IMMEDIATELY.

CONCRETE REPAIR WORK SHALL BE PERFORMED IN A MANNER THAT WILL NOT INTERFERE WITH THOROUGH CURING OF SURROUNDING CONCRETE. MORTAR AND CONCRETE USED IN REPAIR WORK SHALL BE ADEQUATELY CURED AND SHALL BE FINISHED TO MATCH ADJACENT SURFACES.

CONCRETE FOR ENCASED PVC CONDUIT. CONCRETE FOR ENCASED PVC CONDUIT SHALL BE AS SPECIFIED UNDER THE ARTICLE ENTITLED LIMITING REQUIREMENTS EXCEPT THAT IT SHALL HAVE A SLUMP OF 6 INCHES, SHALL CONTAIN AT LEAST 470 POUNDS OF CEMENT PER CUBIC YARD AND SHALL CONTAIN NO AGGREGATE LARGER THAN <sup>3</sup>/<sub>4</sub> INCH. MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS SHALL BE 2,500 PSI. CONCRETE FOR ENCASED PVC CONDUIT SHALL BE COMPACTED BY RODDING OR SPADING ONLY. MECHANICAL VIBRATORS SHALL NOT BE USED. CONCRETE SHALL BE WORKED AROUND REINFORCEMENTS AND EMBEDMENT AND WORKED INTO THE CORNERS OF THE FORMS.

CONCRETE FOR ENCASED PVC CONDUIT MAY BE CAST DIRECTLY AGAINST EARTH WITHOUT THE PROTECTIVE POLYETHYLENE FILM, PROVIDED THE CONTACTED EARTH IS WETTED BEFORE PLACEMENT OF CONCRETE.

FIELD CONTROL TESTING. FIELD CONTROL TESTS CONSISTING OF SLUMP TESTS, AIR CONTENT TESTS, AGGREGATE GRADATION TESTS AND THE PREPARATION OF CONCRETE TEST SPECIMENS SHALL BE MADE BY THE CONTRACTOR. THE CONTRACTOR SHALL PROVIDE FOR MAKING THE TESTS AND TEST SPECIMENS AND FOR STORING, CURING, HANDLING AND DELIVERING TEST SPECIMENS TO A TESTING LABORATORY RETAINED AND PAID BY THE CONTRACTOR.

AIR CONTENT. AN AIR CONTENT TEST SHALL BE MADE EACH DAY CONCRETE 8700 TO 8805 (LAND SURVEYOR'S ACT. IS PLACED. AIR CONTENT SHALL BE DETERMINED IN ACCORDANCE WITH

COMPRESSION TESTS. A SET OF THREE COMPRESSION TEST CYLINDERS SHALL BE MADE EACH DAY CONCRETE IS PLACED. ONE CYLINDER OF EACH SET SHALL BE TESTED AT AN AGE OF 7 DAYS AND ANOTHER AT AN AGE OF

CONCRETE TEST CYLINDERS SHALL BE MADE, CURED, STORED AND DELIVERED TO THE LABORATORY IN ACCORDANCE WITH ASTM C31. THE CYLINDERS SHALL BE TESTED IN ACCORDANCE WITH ASTM C39.

EACH SET OF COMPRESSION TEST CYLINDERS SHALL BE MARKED OR TAGGED WITH THE DATE AND TIME OF DAY THE CYLINDERS WERE MADE. THE LOCATION IN THE WORK WHERE THE CONCRETE WAS PLACED, THE AIR CONTENT, AND THE SLUMP.

AGGREGATE GRADATION. FINE AND COARSE AGGREGATE SHALL BE SAMPLED AND TESTED IN ACCORDANCE WITH ASTM 075 AND C136.

REINFORCEMENT. REINFORCEMENT SHALL BE ACCURATELY FORMED AND POSITIONED AND SHALL BE MAINTAINED IN PROPER POSITION WHILE THE CONCRETE IS BEING PLACED AND COMPACTED. DETAILS OF FABRICATION SHALL CONFORM TO ACI 318-83.

# HOT WEATHER CONCRETING.

EXCEPT AS MODIFIED HEREIN, HOT WEATHER CONCRETING

SHALL COMPLY WITH ACI 305. AT AIR TEMPERATURES OF 90° FOR ABOVE, SPECIAL PROCEDURES SHALL BE ADOPTED TO KEEP THE CONCRETE AS COOL AS POSSIBLE DURING PLACEMENT AND CURING. THE TEMPERATURE OF THE CONCRETE WHEN IT IS PLACED IN THE WORK SHALL NOT EXCEED 90° F. WHENEVER THE AIR TEMPERATURE EXCEEDS 95° F, MEMBRANE CURED SLABS SHALL BE KEPT WET TO PROMOTE COOLING OF THE CONCRETE DURING THE CURING PERIOD.

CURING. CONCRETE SHALL BE PROTECTED FROM LOSS OF MOISTURE FOR AT LEAST 7 DAYS BY POLYETHYLENE FILM OR MEMBRANE CURING COMPOUND. MEMBRANE CURING COMPOUND SHALL BE APPLIED AS RECOMMENDED BY THE MANUFACTURER. CONCRETE SHALL NOT BE PERMITTED TO FREEZE FOR AT LEAST 7 DAYS FOLLOWING PLACEMENT.

THE TOP SURFACE OF THE CONCRETE FOR ENCASED PVC CONDUIT SHALL BE SCREEDED ONLY. NO FLOATING OR TROWELING OF THE SURFACE IS REQUIRED.

CONCRETE JOINT SEALANT, CAULK ALL EXPANSION JOINTS IN CURB AND GUTTER USING A MULTIPLE COMPONENT, SELF-LEVELING POLYURETHANE BASED SEALANT CONFORMING TO ASTM C 620-86, TYPE M, CLASS 25. ACCEPTABLE PRODUCTS INCLUDE, BUT ARE NOT LIMITED TO, THE FOLLOWING:

- MAMECO INTERNATIONAL: VULKEM 245 SIKA
- CORP: SIKAFLEX 2C-SL SONNEBORN BUILDING PRODUCTS: SONOLASTIC PAVING JOINT SEALING TREMCO: THC-900

PRESERVATION OF MONUMENTS AND.STAKES. THE CONTRACTOR SHALL CAREFULLY PRESERVE ALL MONUMENTS, BENCH MARKS, REFERENCE POINTS AND STAKES INSTALLED BY THE OWNER OR OTHERS. PERMANENT MONUMENTS OR BENCHMARKS, WHICH MUST BE REMOVED OR DISTURBED, SHALL BE PROTECTED UNTIL THEY CAN BE PROPERLY REFERENCED FOR RELOCATION THE CONTRACTOR SHALL FURNISH MATERIALS AND ASSISTANCE FOR THE PROPER REPLACEMENT OF SUCH MONUMENTS OR BENCHMARKS.

THE REPLACEMENT OF ALL MONUMENTS AND BENCHMARKS SHALL BE PREFORMED BY A LICENSED CIVIL ENGINEER OR LAND SURVEYOR PURSUANT TO THE BUSINESS AND PROFESSIONS CODE, SECTION

### STANDARD SPECIFICATIONS MATERIALS AND FITTINGS FOR SEWER AND WATER CONSTRUCTION

### SEC. 1 PIPE A. SEWER

PVC

AWWA 3034-PVC SDR-35 AS MANUFACTURED BY VINYLTECH, JOHNS MANVILLE, CERTAINED OR APPROVED EQUAL. HOPE-PRESSURE PIPE MUST MEETAWWA C901 & C906 AND/OR ASTM D 3035 AND F 714 AS MANUFACTURED.

# B. WATER

PVC AWWA C-900 AND C-905 PVC VINYL TECH, JOHNS-MANVILLE, CERTAINED OR ASTM A-536 DUCTILE IRON WITH POLYETHYLENE ENCASEMENT INSTALLED IN ACCORDANCE WITH METHOD A AS MANUFACTURED BY U.S. PIPE OR APPROVED EQUAL. CLASS RATING AND DR DESIGNATION PER APPROVED PLANS. HOPE - GRAVITY FLOW-PIPE MUST MEET REQUIREMENTS OF ASTM D-3350 & ASTM F-894 AS MANUFACTURED BY CHEVRORI CHEMICAL CO. PLEXCO- SPIROLETE, ADS N-12, HANCOR, OR APPROVED EQUAL.

### SEC. 2 VALVES

- A. GATE VALVES 3-INCH AND SMALLER SHALL BE BRONZE, CLASS 200, WITH INSIDE IRON PIPE THREADS.
- B. GATE VALVES 2 1/2-INCH TO 12-INCH SHALL BE OF THE RESILANT WEDGE TYPE IN ACCORDANCE WITH AWWA C-509. GATE VALVES SHALL HAVE "O" RING STEM SEALS FULLY RUBBER ENCAPSULATED WEDGES, MINIMUM 8 MIL FUSION BONDED EPOXY COATED INSIDE AND OUT; ALL EXTERIOR NUTS AND BOLTS MINIMUM T-304 SS; FULL SIZE UNOBSTRUCTED FLOWAY AND LOW ZINC BRONZE NON-RISING STEM MANUFACTURED BY AFC, AVK, MUELLER OR APPROVED EQUAL.
- C. BUTTERFLY VALVES SHALL BE USED IN APPLICATIONS LARGER THAN 12-INCH AND SHALL BE IN ACCORDANCE WITH AWWA C-504 FOR BURIED SERVICE. BUTTERFLY VALVES SHALL BE CLASS 150B OF THE SHORT-BODY, FLANGED CONFIGURATION, EQUIPPED WITH MANUAL OPERATORS WITH OPERATOR NUT IN ACCORDANCE WITH AWWA C-500, MINIMUM 8 MIL FUSION BONDED EPOXY COATED INSIDE AND OUT; ALL EXTERIOR NUTS AND BOLTS MINIMUM T-304 SS AS MANUFACTURED BY MUELLER, PRATT, KEYSTONE OR APPROVED EQUAL.

### SEC. 3 FITTINGS

FITTINGS SHALL BE DUCTILE IRON MECHANICAL JOINT OR PUSH-ON IN ACCORDANCE WITH AWWA C-110, C-111 AND C-153. THE WORKING PRESSURE SHALL BE 350 PSI. INTERIORS SHALL LINED AND SEAL COATED IN ACCORDANCE WITH AWWA C-104 AS MANUFACTURED BY TYLER PIPE, STAR PIPE OR APPROVED EQUAL. ALL NUTS, BOLTS AND OTHER HARDWARE THAT ARE NOT T-304 SS SHALL BE WRAPPED WITH 4 LAYERS OF 10 MIL SHEETING AND TAPED WITH PVC TAPE PRIOR TO BACKFILL AND/OR THRUST BLOCK PLACEMENT HOPE - FITTING SHALL BE HOPE (MEET ASTM 2513 REQUIREMENTS) BUTT FUSION FITTINGS MEETING REQUIREMENTS OF ASTM D 3261-SCOKE FITTING SHALL MEET ASTM 2683 REQUIREMENTS BY PHILLIPS DRISCOPIPE, INC., CHEVRON CHEMICAL CO. PLEXCO, OR APPROVED EQUAL.

### SEC. 4 GASKETS

GASKETS FOR FLANGED FITTINGS SHALL BE IN ACCORDANCE WITH AWWA C-110 AND C-115, WITH WORKING PRESSURE OF 350 PSI AS MANUFACTURED BY U.S. PIPE OF APPROVED EQUAL.

### SEC. 5 NUTS AND BOLTS

ALL NUTS AND BOLTS BURIED BELOW GRADE SHALL BE MINIMUM T-304 SS IN ACCORDANCE WITH ASTM F 593 & F 594. ALL THREADS SHALL BE COATED ACCORDING TO THE MANUFACTURER'S RECOMMENDATION WITH AN ANTI-SEIZE COMPOUND SUCH AS PEMATEX PART NO. 133K OR APPROVED EQUAL.

### SEC. 6 COPPER TUBING

COPPER TUBING SHALL CONFORM TO ASTM B 88; TYPE K-SOFT 2-INCH COPPER TUBING SHALL BE IN 20-FOOT LENGTHS AND NOT COILS.

### SEC. 7 SOLDER

SOLDER FOR WELDING COPPER TUBING SHALL BE SIL-CAN 15 CONTAINING 15 PERCENT SILVER WITH A BRAZING TEMPERATURE OF 1300°F AS MANUFACTURED BY

M.C. CANFIELD SONS OR APPROVED EQUAL.

### SEC. 7 THRUST BLOCKS

THRUST BLOCKS SHALL BE CONSTRUCTED OF TYPE V-CLASS 3 CONCRETE.


### SEC. 8 TAPPING SLEEVES

TAPPING SLEEVES SHALL BE ALL STAINLESS STEEL T-304 AND BE IN ACCORDANCE WITH AWWA C-207 WITH WORKING PRESSURE OF 350 PSI AS MANUFACTURED BY CASCADE WATERWORKS OR APPROVED EQUAL.


### SEC. 9 RESTRAINED JOINTS

SEC.10 MATERIALS AND FITTINGS REFERENCED IN STANDARD DRAWINGS

ALL MATERIALS AND FITTINGS REFERENCED IN STANDARD DRAWINGS SHALL BE PROVIDED AS INDICATED.







**REVISIONS:** 

UNAUTHORIZED CHANGES & USES: The engineer preparing these plans will not be for, or liable for, unauthorized changes to or uses of these plans. All changes to the pla must be in writing and must be approved by the preparer of these plans.

	APPROVED DATE	DESIGN BY:	ELEVATION: <u>EL= 391.57'</u>		PREPARED UNDER THE DIRECT SUPERVISION OF	F:		SHEET
		VG	LOCATION: SET ON TOP OF 2-INCH BRASS DISK ON A CONCRETE MONUMENT	SED BERT K. MA			PARKING LOT IMPROVEMENTS IN THE CITY OF BLYTHE, CALIFORNIA	14
		DRAWN BY:	STAMPED "FLY 1948", NATIONAL GEODETIC SURVEY 1981 13.0 KM (8.1 MI) WEST FROM BLYTHE. 13.0 KM (8.1 MI) WEST ALONG HOBSONWAY FROM THE JUNCTION OF U.S. HIGHWAY 95 IN BLYTHE, 102.1 METERS (235 FT)	ER St.	"North . Alt		SHEET CONTENT:	
		VG	SOUTH-SOUTHWEST OF THE SOUTHWEST CORNER OF A BUILDING BELONGING TO THE BLYTHE TRAP SHOOT CLUB, 39.3 METERS (129 FT) NORTH ACROSS A GRAVEL ROAD FROM THE CENTERLINE OF	Lu Po. 27943	ROBERT K. HOLT, P.E.	27943 R.C.E. NO.	DETAIL SHEET	OF 14 SHEETS
			HOBSONWAY, 26.8 METERS (88.0 FT) NORTH OF A BARBED WIRE RIGHT-OF-WAY FENCE, 24.9 METERS (81.7 FT) NORTH OF THE FIRST	Exp. 03-81-24 03 90122*				
e responsible lans		CHECKED BY:	POWER POLE WEST OF A SPUR LINE TO THE TRAP CLUB, 13.2 METERS (43.5 FT) NORTH OF THE CENTERLINE OF THE GRAVEL ROAD. THE MARK	PAR CIVIL OF CALIFORN	09-01-2022	03/31/24		JOB NO.
		RKH	ÌS 2.35 METERS N FROM À WITNESS POST. THE MARK IS ABOVE LEVEL WITH HOBSONWAY. EL= 391.57'	GRE	DATE	REG. EXP.	LOCATION: BLYTHE, CA. CLIENT: PALO VERDE COLLEGE	533.007